# SONY

Diagonal 11.1 mm (Type 2/3) CMOS solid-state Image Sensor with Square Pixel for Color Cameras

# **IMX264LQR-C**



For the latest data sheet, please visit www.sunnywale.com

### **Description**

The IMX264LQR-C is a diagonal 11.1 mm (Type 2/3) CMOS active pixel type solid-state image sensor with a square pixel array and 5.07 M effective pixels. This chip features a global shutter with variable charge-integration time. This chip operates with analog 3.3 V, digital 1.2 V, and interface 1.8 V triple power supply, and has low power consumption. High sensitivity, low dark current and low PLS characteristics are achieved.

(Applications: FA cameras, ITS cameras)

#### **Features**

- ◆ CMOS active pixel type dots
- ◆ Built-in timing adjustment circuit, H/V driver and serial communication circuit
- Global shutter function
- ◆ Input frequency 37.125 MHz / 74.25 MHz / 54 MHz
- ♦ Number of recommended recording pixels: 2448 (H) x 2048 (V) approx. 5.01 M pixels

Readout mode

All-pixel scan mode

1080p-Full HD readout mode

Vertical / Horizontal 1 / 2 Subsampling mode

ROI mode

Vertical / Horizontal - Normal / Inverted readout mode

◆ Readout rate

Maximum frame rate in

All-pixel scan mode: 12 bit: 35.7 frame/s

- ◆ Variable-speed shutter function (resolution 1 H units)
- ◆ 12-bit A/D converter
- ◆ CDS / PGA function

0 dB to 24 dB: Analog Gain (0.1 dB step)

24.1 dB to 48 dB: Analog Gain: 24 dB + Digital Gain: 0.1 dB to 24 dB (0.1 dB step)

♦ I/O interface

Low voltage LVDS (150 mVp-p) serial (4 ch) DDR output

- ◆ Recommended lens F number: 2.8 or more (Close side)
- ◆ Recommended exit pupil distance: -100 mm to -∞



Sony reserves the right to change products and specifications without prior notice.

This information does not convey any license by any implication or otherwise under any patents or other right.

Application circuits shown, if any, are typical examples illustrating the operation of the devices. Sony cannot assume responsibility for any problems arising out of the use of these circuits.

1

E15X05C66

#### **Device Structure**

◆ CMOS image sensor

◆ Image size

Diagonal 11.1 mm (Type 2/3) Approx. 5.07 M pixels All-pixel
Diagonal 7.7 mm (Type 1/2.35) Approx. 2.11 M pixels 1080p-Full HD

◆ Total number of pixels

2464 (H) x 2066 (V) Approx. 5.09 M pixels

◆ Number of effective pixels

2464 (H) x 2056 (V) Approx. 5.07 M pixels

◆ Number of active pixels

2464 (H) x 2056 (V) Approx. 5.07 M pixels

◆ Number of recommended recording pixels

2448 (H)  $\times$  2048 (V) Approx. 5.01 M pixels All-pixel 1920 (H)  $\times$  1080 (V) Approx. 2.07 M pixels 1080p-Full HD

◆ Unit cell size 3.45 µm (H) x 3.45 µm (V)

◆ Optical black

Horizontal (H) direction: Front 0 pixels, rear 0 pixels Vertical (V) direction: Front 10 pixels, rear 0 pixels

Substrate material Silicon

# **Absolute Maximum Ratings**

Item	Symbol	Rating			Unit	Remarks
Supply voltage (Analog 3.3 V)	AV <sub>DD</sub>	-0.3	to	+4.0	V	
Supply voltage (Interface 1.8 V)	$OV_{DD}$	-0.3	to	+3.3	V	
Supply voltage (Digital 1.2 V)	DV <sub>DD</sub>	-0.3	to	+2.0	V	
Input voltage	VI	-0.3	to	OV <sub>DD</sub> +0.3	V	Not exceed 3.3 V
Output voltage	VO	-0.3	to	OV <sub>DD</sub> +0.3	V	Not exceed 3.3 V
Operating temperature	Topr	-30	to	+75	°C	
Storage temperature	Tstg	-40	to	+85	°C	
Performance guarantee temperature	Tspec	-10	to	+60	°C	

# **Recommended Operating Conditions**

Item	Symbol	Min.	Тур.	Max.	Unit
Supply voltage (Analog 3.3 V)	$AV_DD$	3.15	3.30	3.45	V
Supply voltage (Interface 1.8 V)	$OV_DD$	1.70	1.80	1.90	V
Supply voltage (Digital 1.2 V)	$DV_DD$	1.10	1.20	1.30	V

#### **USE RESTRICTION NOTICE**

This USE RESTRICTION NOTICE ("Notice") is for customers who are considering or currently using the image sensor products ("Products") set forth in this specifications book. Sony Corporation ("Sony") may, at any time, modify this Notice which will be available to you in the latest specifications book for the Products. You should abide by the latest version of this Notice. If a Sony subsidiary or distributor has its own use restriction notice on the Products, such a use restriction notice will additionally apply between you and the subsidiary or distributor. You should consult a sales representative of the subsidiary or distributor of Sony on such a use restriction notice when you consider using the Products.

#### **Use Restrictions**

- The Products are intended for incorporation into such general electronic equipment as office products, communication products, measurement products, and home electronics products in accordance with the terms and conditions set forth in this specifications book and otherwise notified by Sony from time to time.
- You should not use the Products for critical applications which may pose a life- or injury-threatening
  risk or are highly likely to cause significant property damage in the event of failure of the Products. You
  should consult your sales representative beforehand when you consider using the Products for such
  critical applications. In addition, you should not use the Products in weapon or military equipment.
- Sony disclaims and does not assume any liability and damages arising out of misuse, improper use, modification, use of the Products for the above-mentioned critical applications, weapon and military equipment, or any deviation from the requirements set forth in this specifications book.

#### **Design for Safety**

Sony is making continuous efforts to further improve the quality and reliability of the Products; however, failure of a certain percentage of the Products is inevitable. Therefore, you should take sufficient care to ensure the safe design of your products such as component redundancy, anti-conflagration features, and features to prevent mis-operation in order to avoid accidents resulting in injury or death, fire or other social damage as a result of such failure.

#### **Export Control**

 If the Products are controlled items under the export control laws or regulations of various countries, approval may be required for the export of the Products under the said laws or regulations.
 You should be responsible for compliance with the said laws or regulations.

#### No License Implied

• The technical information shown in this specifications book is for your reference purposes only. The availability of this specifications book shall not be construed as giving any indication that Sony and its licensors will license any intellectual property rights in such information by any implication or otherwise. Sony will not assume responsibility for any problems in connection with your use of such information or for any infringement of third-party rights due to the same. It is therefore your sole legal and financial responsibility to resolve any such problems and infringement.

#### **Governing Law**

This Notice shall be governed by and construed in accordance with the laws of Japan, without reference
to principles of conflict of laws or choice of laws. All controversies and disputes arising out of or relating
to this Notice shall be submitted to the exclusive jurisdiction of the Tokyo District Court in Japan as the
court of first instance.

#### **Other Applicable Terms and Conditions**

The terms and conditions in the Sony additional specifications, which will be made available to you when
you order the Products, shall also be applicable to your use of the Products as well as to this
specifications book. You should review those terms and conditions when you consider purchasing
and/or using the Products.

General-0.0.8


### **CONTENTS**

Description	1
Features	1
Device Structure	2
Absolute Maximum Ratings	3
Recommended Operating Conditions	3
USE RESTRICTION NOTICE	Δ
Chip Center and Optical Center	
Pixel Arrangement	8
Block Diagram and Pin Configuration	
Pin Description	11
Electrical Characteristics	15
DC Characteristics	15
Power Consumption	15
AC Characteristics	16
Master Clock (INCK) Waveform Diagram	16
XVS / XHS Input Characteristics in Slave Mode (XMASTER = High)	17
XTRIG Input Characteristics in Slave Mode (XMASTER = High) only	17
Serial Communication	
DLCKP1 / DLCKM1, DLOPx1 / DLOMx1	20
I/O Equivalent Circuit Diagram	21
Spectral Sensitivity Characteristics	22
Image Sensor Characteristics	
Zone Definition of Video Signal Shading	
Image Sensor Characteristics Measurement Method	24
Measurement Conditions	24
Color Coding of Physical Pixel Array	24
Definition of standard imaging conditions	24
Measurement Method	
Setting Registers Using Serial Communication	
Description of Setting Registers (4-wire)	
Register Communication Timing (4-wire)	
Register Write and Read (4-wire)	28
Description of Setting Registers (I <sup>2</sup> C)	29
Register Communication Timing (I <sup>2</sup> C)	30
I <sup>2</sup> C Communication Protocol	
I <sup>2</sup> C Serial Communication Read/Write Operation	
Single Read from Random Location	
Single Read from Current Location	
Sequential Read Starting from Random Location	
Sequential Read Starting from Current Location	
Register Map	34
Chip ID = 02 (Write: Chip ID = 02h, Read: Chip ID = 82h, I <sup>2</sup> C: 30**h)	
Chip ID = 03 (Write: Chip ID = 03h, Read: Chip ID = 83h, I <sup>2</sup> C: 31**h)	
Chip ID = 04 (Write: Chip ID = 04h, Read: Chip ID = 84h, I <sup>2</sup> C: 32**h)	
Chip ID = 05 (Write: Chip ID = 05h, Read: Chip ID = 85h, I <sup>2</sup> C: 33**h)	
Chip ID = 06 (Write: Chip ID = 06h, Read: Chip ID = 86h, I <sup>2</sup> C: 34**h)	
Chip ID = 07 (Write: Chip ID = 07h, Read: Chip ID = 87h, I <sup>2</sup> C: 35**h)	
Chip ID = 08 (Write: Chip ID = 08h, Read: Chip ID = 88h, I <sup>2</sup> C: 36**h)	
Chip ID = 09 (Write: Chip ID = 09h, Read: Chip ID = 89h, I <sup>2</sup> C: 37**h)	
Chip ID = 0A (Write: Chip ID = 0Ah, Read: Chip ID = 8Ah, $I^2$ C: 38**h)	
Chip ID = 0C (Write: Chip ID = 0Ch, Read: Chip ID = 8Ch, $I^2$ C: $3A^{**}h$ )	
Chip ID = 0D (Write: Chip ID = 0Dh, Read: Chip ID = 8Dh, I C: $3C^*h$ )	
Chip ID = 0E (Write: Chip ID = 0Eh, Read: Chip ID = 8Eh, I C: 3C**h)	
Chip ID = 0F (Write: Chip ID = 0Fh, Read: Chip ID = 8Fh, I C: 3D**n)	
Chip ID = 10 (Write: Chip ID = 10h, Read: Chip ID = 90h, I C: 3E**h)	
Chip ID = 11 (Write: Chip ID = 111), Read: Chip ID = 911, 1 C: 3F 11)	
OTHER TO - TEXTRICO, OTHER TO - TELL, MODIC, OTHER TO - BELL, I OT - BUT HIMMAN	

### SONY


Readout Drive Modes	45
Sync code	46
List of Sync Code	46
Sync Code Output Timing	46
Image Data Output Format	47
All-pixel scan	47
1080p-Full HD mode	49
ROI mode	51
Vertical / Horizontal 1/2 Subsampling mode	55
Description of Various Function	56
Standby mode	56
Slave Mode and Master Mode	57
Gain Adjustment Function	58
Black Level Adjustment Function	59
Horizontal / Vertical Normal Operation and Inverted Operation	60
Shutter and Integration Time Settings	61
Global Shutter (Normal Mode) Operation	62
Global Shutter (Sequential Trigger Mode) Operation	64
Global Shutter (Fast Trigger Mode) Operation	66
Mode Transitions of Global Shutter Operation	
Pulse Output Function	69
Signal Output	71
Output Pins	71
Output Pin Bit Width	72
Output Signal Range	72
Register Hold Setting	73
Mode Transition	74
Other Function	75
Extension Function	75
Power-on and Power-off Sequence	76
Power-on sequence	76
Power-off Sequence	77
Sensor Setting Flow	78
Setting Flow in Sensor Slave Mode	78
Setting Flow in Sensor Master Mode	79
Peripheral Circuit	80
Analog Power Pins	80
Digital Power Pins	81
Analog Other Pins	82
Digital I/O Pins	83
Output pins	84
Spot Pixel Specifications	85
Sport Pixel Zone Definition	85
Notice on White Pixels Specifications	86
Measurement Method for Spot Pixels	87
Spot Pixel Pattern Specification	88
Marking	89
Notes On Handling	90
Package Outline	92
List of Trademark Logos and Definition Statements	93

### **Chip Center and Optical Center**



Optical Center


### **Pixel Arrangement**




Pixel Arrangement

# **Block Diagram and Pin Configuration**

(Top View)



Block Diagram



Pin Configuration

### **Pin Description**

No.	Pin No.	I/O	Analog/ Digital	Symbol	Description
	A1	1/0	Analog/ Digital	N.C.	Description
1	A3			N.C.	_
2					_
3	A4	<u> </u>	_	N.C.	_
4	A5		_	N.C.	_
5	A6		_	N.C.	_
6	A7	GND ·	A	VRLWSS	3.3V GND
7	A8		Α	VRLSEL	Connect to VCP1
8	A9	GND	Α	VSSHPX	3.3V GND
9	A10	_	_	N.C.	_
10	A11	_	_	N.C.	_
11	A12	_	_	N.C.	_
12	A13	_	_	N.C.	_
13	A14	_	_	N.C.	_
14	A16	_	_	N.C.	_
15	B3	_	_	N.C.	_
16	B4	Power	Α	VDDSUB	3.3V power supply
17	B5	Power	Α	VDDHPX	3.3V power supply
18	B6	_	_	N.C.	_
19	B7	I	А	VRLTRX	Connect to VCP1
20	B8	I	А	VRLOFG	Connect to VCP1
21	B9	Power	A	VDDHAN	3.3V power supply
22	B10	_	_	N.C.	— — — — — — — — — — — — — — — — — — —
23	B11	_	_	N.C.	_
24	B12	Power	Α	VDDHTM	3.3V power supply
25	B13	- T OWCI	_	N.C.	—
26	B14	_		N.C.	
27	C1	<del></del>		N.C.	
28	C2	Power	A	VDDHCM	2.2\/ nower gupply
29	C3	GND	A	VSSHCM	3.3V power supply 3.3V GND
30	C4	GND	A	VSSHPX	3.3V GND
31	C5	GND	A	VSSHPX	3.3V GND
32	C6	<u> </u>	A	VRLTRG	Connect to VCP2
33	C7	0	Α	VCP1	Connect to VRLSEL, VRLTRX, VRLOFG
	00	ONE		\ (D)	(Connect to 4.7 μF × 2 to GND)
34	C8	GND	A	VRLGND	3.3V GND
35	C9	GND	A	VSSHAN	3.3V GND
36	C10	0	Α	VBGR	Connect to 0.22 µF to GND
37	C11	GND	Α	VRLRST	3.3V GND
38	C12	GND	A	VSSHTM	3.3V GND
39	C13	_	_	N.C.	=
40	C14	GND	Α	VSSHCM	3.3V GND
41	C15	Power	Α	VDDHCM	3.3V power supply
42	C16		_	N.C.	_
43	D1	_	_	N.C.	_
44	D2	Power	Α	VDDLCB	1.2V power supply
45	D3	GND	Α	VSSHCM	3.3V GND
46	D4			N.C.	
47	D5	_	_	N.C.	_
48	D6	0	Α	VCP2	Connect to VRLTRG (Connect to 4.7 µF x 2 to GND)
49	D7	GND	Α	VSSHCP	3.3V GND
50	D8	GND	Α	VSSHPX	3.3V GND
51	D9		_	N.C.	_
52	D10	GND	А	VSSHAN	3.3V GND
53	D11	GND	A	VSSHPX	3.3V GND
54	D12			N.C.	—
55	D13	_	_	N.C.	_
56	D13	GND	Α	VSSHCM	3.3V GND
57	D14	Power	A	VDDLCB	1.2V power supply
58	D15	1 OWEI		N.C.	
	E1		<u> </u>	N.C.	
59		<del></del>	<u> </u>		<del>-</del>
60	E2	<u> </u>	_	N.C.	
61	E3			N.C.	_

SONY IMX264LQR-C

No.	Pin No.	I/O	Analog/ Digital	Symbol	Description
62	E4	GND	A	VSSHPX	3.3V GND
63	E5	GND	A	VSSHPX	3.3V GND
64	E6	GND	A	VSSHPX	3.3V GND
65	E7	GND	A	VSSHPX	3.3V GND
66	E8	GND	A	VSSHPX	3.3V GND
				VSSHPX	
67	E9	GND	A		3.3V GND
68	E10	GND	A	VSSHAN	3.3V GND
69	E11	GND	Α	VSSHPX	3.3V GND
70	E12		_	N.C.	_
71	E13	_	_	N.C.	_
72	E14	_	_	N.C.	_
73	E15	1	1	N.C.	_
74	E16	_	_	N.C.	_
75	F1	0	D	TOUT0	Pulse0 output pin
76	F2	0	D	TOUT2	Pulse2 output pin
77	F3	_	_	N.C.	_
78	F4	_	_	N.C.	_
79	F5	Power	A	VDDHTRX	3.3V power supply
80	F6	Power	A	VDDHTRG	3.3V power supply
81	F7	Power	A	VDDHTRG	3.3V power supply
82	F8	Power	A	VDDHOFG	3.3V power supply
83	F9	Power	A	VDDHSEL	3.3V power supply
84	F10	Power	Α	PVLM	1.2V power supply
85	F11	Power	Α	VDDHPX	3.3V power supply
86	F12			N.C.	_
87	F13	-	_	N.C.	_
88	F14		_	N.C.	_
89	F15	GND	D	VSSLSC	1.2V GND
90	F16	Power	D	VDDLSC	1.2V power supply
91	G1	Power	D	VDDLSC	1.2V power supply
92	G2	GND	D	VSSLSC	1.2V GND
93	G3	0	D	TOUT1	Pulse1 output pin
94				VSSHCP	
	G4	GND	A		3.3V GND
95	G5	Power	A	VDDHCP	3.3V power supply
96	G12	_		N.C.	_
97	G13	_	_	N.C.	_
98	G14	-	_	N.C.	_
99	G15	_	_	N.C.	_
100	G16	1	_	N.C.	_
101	H1	GND	D	VSSH	3.3V GND
102	H2	GND	D	VSSH	3.3V GND
103	H3	_	_	N.C.	_
104	H4	GND	А	VSSHPX	3.3V GND
105	H5	Power	A	VDDHPX	3.3V power supply
106	H12	Power	A	VDDLCB	1.2V power supply
107	H13	GND	A	VSSHCM	3.3V GND
108	H14	— — — — — — — — — — — — — — — — — — —		N.C.	
109	H15	GND	D	VSSLCN	1.2V GND
110	H16	Power	D	VDDLCN	1.2V power supply
111	J1	Power	D	VDDLCN	1.2V power supply
112	J2	GND	D	VSSLCN	1.2V GND
113	J3	1	D	XMASTER	Master / Slave select
					(Slave Mode: High, Master Mode: Low)
114	J4	GND	Α	VSSHCM	3.3V GND
115	J5	Power	Α	VDDHCM	3.3V power supply
116	J12	Power	Α	VDDHCM	3.3V power supply
117	J13	GND	Α	VSSHCM	3.3V GND
118	J14	_	_	N.C.	_
119	J15	_	_	N.C.	_
120	J16	_	_	N.C.	_
121	K1	I	D	SLAMODE	Slave address select (1A: High, 10: Low)
122	K2	<u> </u>		N.C.	
123	K3		D	XCLR	System clear (Normal: High, Clear: Low)
		•			3.3V GND
124	K4	GND	A	VSSHCM	
125	K5	Power	Α	VDDLCB	1.2V power supply

IMX264LQR-C

SONY

No.	Pin No.	I/O	Analog/ Digital	Symbol	Description
126	K12	Power	Arialog/ Digital	VDDHPX	3.3V power supply
127	K12	GND	A	VSSHPX	3.3V GND
128	K13	GND	A	N.C.	3.37 GND
129	K14	GND	D	VSSLCN	1.2V GND
130	K16	Power	D	VDDLCN	1.2V GND
			Ь		4-wire: Serial communication I/F SDO pin
131	L1	0	D	SDO	I <sup>2</sup> C: OPEN
132	L2	1	D	XCE	4-wire: Serial communication I/F XCE pin I <sup>2</sup> C: Fixed to High
133	L3	1	D	SCK / SCL	4-wire: Serial communication I/F SCK pin I <sup>2</sup> C: Serial clock line
134	L4	GND	Α	VSSHPX	3.3V GND
135	L5	Power	Α	VDDHPX	3.3V power supply
136	L12	_	_	N.C.	_
137	L13	1	_	N.C.	_
138	L14	_	_	N.C.	_
139	L15		_	N.C.	_
140	L16	_	_	N.C.	_
141	M1	Power	D	VDDLSC	1.2V power supply
142	M2	GND	D	VSSLSC	1.2V GND
143	МЗ	I/O	D	SDI / SDA	4-wire: Serial communication I/F SDI pin I <sup>2</sup> C: Serial data line
144	M4	_	_	N.C.	_
145	M5	_	_	N.C.	_
146	M6	GND	D	VSSLSC	1.2V GND
147	M7	Power	D	VDDMIO	1.8V power supply
148	M8	GND	D	VSSLSC	1.2V GND
149	M9	Power	D	VDDLSC	1.2V power supply
150	M10	Power	D	VDDLPA	1.2V power supply
151	M11	GND	D	VSSLPA	1.2V GND
152	M12	_	_	N.C.	_
153	M13	_	_	N.C.	_
154	M14	1	_	N.C.	_
155	M15	GND	D	VSSLSC	1.2V GND
156	M16	Power	D	VDDLSC	1.2V power supply
157	N1	I/O	D	XVS	Vertical sync signal
158	N2	I/O	D	XHS	Horizontal sync signal
159	N3	I	D	XTRIG	Trigger input
160	N4	_	_	N.C.	_
161	N5	GND	D	VSSMIF	1.8V GND
162	N6	GND	D	VSSMIF	1.8V GND
163	N7	GND	D	VSSMIF	1.8V GND
164	N8	Power	D	VDDMIF	1.8V power supply
165	N9	Power	D	VDDMIF	1.8V power supply
166	N10	GND	D	VSSMIF	1.8V GND
167	N11	GND	D	VSSMIF	1.8V GND
168	N12	GND	D	VSSMIF	1.8V GND
169	N13	_		N.C.	_
170	N14	_	_	N.C.	_
171	N15		_	N.C.	_
172	N16 P1	_		N.C.	_
173 174	P1 P2	_		N.C.	_
174	P2 P3		_	N.C.	<u>-</u>
175	P3	0	 D	DLOPC1	Low Voltage LVDS serial output (Data)
176	P5	0	D	DLOPC1 DLOPD1	Low Voltage LVDS serial output (Data)  Low Voltage LVDS serial output (Data)
177	P6	0	D	DLOPD1 DLOPF1	Low Voltage LVDS serial output (Data)  Low Voltage LVDS serial output (Data)
179	P7			N.C.	Low voltage Evido serial output (Data)
180	P8	 GND	D	VSSMIF	
181	P9	GND	D	VSSMIF	1.8V GND
182	P10	- GIVD	_	N.C.	1.07 SIND
183	P11			N.C.	
184	P12			N.C.	_
185	P13			N.C.	_
186	P14		_	N.C.	_
100	1 17			14.0.	

No.	Pin No.	I/O	Analog/ Digital	Symbol	Description
187	P15	_	—	N.C.	_
188	P16	_	_	N.C.	_
189	R1	_	_	N.C.	_
190	R2	_	_	N.C.	_
191	R3	_	_	N.C.	_
192	R4	0	D	DLOMC1	Low Voltage LVDS serial output (Data)
193	R5	0	D	DLOMD1	Low Voltage LVDS serial output (Data)
194	R6	0	D	DLOMF1	Low Voltage LVDS serial output (Data)
195	R7		_	N.C.	
196	R8	GND	D	VSSMIF	1.8V GND
197	R9	GND	D	VSSMIF	1.8V GND
198	R10	_	_	N.C.	_
199	R11	_	_	N.C.	_
200	R12	1	_	N.C.	_
201	R13		_	N.C.	_
202	R14	_	_	N.C.	_
203	R15	_	_	N.C.	_
204	R16		_	N.C.	_
205	T3	I	_	N.C.	_
206	T4		_	N.C.	_
207	T5	0	D	DLCKP1	Low Voltage LVDS serial output (Clock)
208	T6	0	D	DLOPE1	Low Voltage LVDS serial output (Data)
209	T7	_	_	N.C.	_
210	T8	_	_	N.C.	_
211	T9	_	_	N.C.	_
212	T10	_	_	N.C.	_
213	T11	_	_	N.C.	_
214	T12	_	_	N.C.	_
215	T13	_	_	N.C.	_
216	T14	_	_	N.C.	_
217	U1	_	_	N.C.	_
218	U3	_	_	N.C.	_
219	U4		_	N.C.	_
220	U5	0	D	DLCKM1	Low Voltage LVDS serial output (Clock)
221	U6	0	D	DLOME1	Low Voltage LVDS serial output (Data)
222	U7		_	N.C.	_
223	U8	GND	D	VSSLSC	1.2V GND
224	U9	I	D	INCK	Master clock input
225	U10		_	N.C.	_
226	U11		_	N.C.	_
227	U12	_	_	N.C.	_
228	U13		_	N.C.	_
229	U14			N.C.	_
230	U16	_	_	N.C.	_

<sup>\*</sup> N.C. pins in the table above should be left open on the board.


SONY

### **Electrical Characteristics**

#### **DC Characteristics**

Item		Pins	Symbol	Conditions	Min.	Тур.	Max.	Unit		
	Analog	V <sub>DD</sub> Hx	$AV_DD$	_	3.15	3.30	3.45	V		
Supply voltage	Interface	V <sub>DD</sub> Mx	$OV_DD$	_	1.70	1.80	1.90	V		
	Digital	V <sub>DD</sub> Lx	$DV_{DD}$	_	1.10	1.20	1.30	V		
Digital input voltage		XHS XVS XCLR INCK	VIH		0.8 × OV <sub>DD</sub>	_	_	V		
		XMASTER SLAMODE SCK SDI XCE XTRIG	VIL	XVS / XHS in Slave mode	_	_	0.2 × OV <sub>DD</sub>	V		
			DLOPx1 DLOMx1 VCM DCKP1		VCM	Low voltage LVDS	_	OV <sub>DD</sub> /2	_	V
Digital output			VOD	(termination resistance: 100 Ω)	100	150	210	mV		
Digital output voltage		XHS XVS	VOH	XVS / XHS	OV <sub>DD</sub> -0.4		_	V		
		SDO TOUT1 TOUT2	VOL	in Master mode	_	_	0.4	V		





### **Power Consumption**

Item	Pins	Symbol	Тур.	Max.	Unit
Operating current	V <sub>DD</sub> H	IAV <sub>DD</sub>	120	175	mA
Serial LVDS 4 ch	$V_{DD}M$	IOV <sub>DD</sub>	11	20	mA
12 bit 35.7 frame/s	V <sub>DD</sub> L	$IDV_{DD}$	120	180	mA
Standby current	$V_{DD}H$	IAV <sub>DD</sub> _STB	_	0.5	mA
	$V_{DD}M$	IOV <sub>DD</sub> _STB	1	0.5	mA
	V <sub>DD</sub> L	IDV <sub>DD</sub> _STB	_	20	mA

Operating current:

(Typical value condition): Supply voltage: 3.30 V / 1.80 V / 1.20 V, Tj =  $25 ^{\circ}\text{C}$  (Maximum value condition): Supply voltage: 3.45 V / 1.90 V / 1.30 V, Tj =  $60 ^{\circ}\text{C}$ 

Worst state of internal circuit operating current consumption.


Standby current:

(Maximum value condition): Supply voltage: 3.45 V / 1.90 V / 1.30 V, Tj =  $60 ^{\circ}$ C, INCK = 0 V,

The device in the light-obstructed state.

### **AC Characteristics**


### Master Clock (INCK) Waveform Diagram



Item	Symbol	Min.	Тур.	Max.	Unit	Remarks
INCK clock frequency	f <sub>INCK</sub>	f <sub>INCK</sub> × 0.96	finck	f <sub>INCK</sub> × 1.02	MHz	f <sub>INCK</sub> = 37.125 MHz, 74.25 MHz, 54 MHz
INCK Low level pulse width	t <sub>WLINCK</sub>	4	_	_	ns	
INCK High level pulse width	t <sub>WHINCK</sub>	4	_	_	ns	
INCK clock duty	_	45.0	50.0	55.0	%	Define with 0.5 × OV <sub>DD</sub>

<sup>\*</sup> The INCK fluctuation affects the frame rate.


### XVS / XHS Input Characteristics in Slave Mode (XMASTER = High)



Item	Symbol	Min.	Тур.	Max.	Unit
XHS Low level pulse width	twlxHs	4/f <sub>INCK</sub>	_	_	ns
XHS High level pulse width	twhxhs	4/f <sub>INCK</sub>	_	_	ns
XVS - XHS fall width	t <sub>HFDLY</sub>	1/f <sub>INCK</sub>	_	_	ns
XHS - XVS rise width	t <sub>VRDLY</sub>	1/f <sub>INCK</sub>	_	_	ns

Synchronization cannot be performed from XVS and XHS signal in mater mode. Detect the sync code.


# XTRIG Input Characteristics in Slave Mode (XMASTER = High) only



Item	Symbol	Min.	Тур.	Max.	Unit
XTRIG fall - XHS fall width	t <sub>TGHDLYF</sub>	10	_	HMAX-10	INCK
XTRIG rise - XHS fall width	t <sub>TGHDLYR</sub>	10	_	HMAX-10	INCK


### **Serial Communication**

### 4-wire



Item	Symbol	Min.	Тур.	Max.	Unit	Remarks
SCK clock frequency	f <sub>SCK</sub>	_	_	13.5	MHz	
XCLR Low level pulse width	t <sub>WLXCLR</sub>	4/f <sub>INCK</sub>	_	_	ns	
INCK effective margin	t <sub>ENINCK</sub>	1	_	_	μs	
XCE effective margin	t <sub>ENXCE</sub>	20	_	_	μs	
XCE input setup time	t <sub>SUXCE</sub>	20	_	_	ns	
XCE input hold time	t <sub>HDXCE</sub>	20	_	_	ns	
XCE High level pulse width	t <sub>WHXCE</sub>	20	_	_	ns	
SDI input setup time	t <sub>SUSDI</sub>	10	_	_	ns	
SDI input hold time	t <sub>HDSDI</sub>	10	_	_	ns	
SDO output delay time	t <sub>DLSDO</sub>	0	_	25	ns	Output load capacitance: 20 pF

 $I^2C$ 




# I<sup>2</sup>C Specification

Item	Symbol	Min.	Тур.	Max.	Unit	Remarks
Low level input voltage	V <sub>IL</sub>	-0.3	_	0.3 × OV <sub>DD</sub>	V	
High level input voltage	V <sub>IH</sub>	0.7 × OV <sub>DD</sub>	_	1.9	V	
Low level output voltage	V <sub>OL</sub>	0	_	$0.2 \times OV_{DD}$	V	OV <sub>DD</sub> < 2 V, Sink 3 mA
High level output voltage	V <sub>OH</sub>	0.8 × OV <sub>DD</sub>	_	_	V	
Output fall time	tof	_	_	250	ns	Load 10 pF – 400 pF, 0.7 × OV <sub>DD</sub> – 0.3 × OV <sub>DD</sub>
Input current	li	-10	_	10	μA	$0.1 \times OV_{DD} - 0.9 \times OV_{DD}$
Capacitance for SCK (/SCL) , SDI (/SDA)	Ci	_	_	10	pF	

# I<sup>2</sup>C AC Characteristics

Item	Symbol	Min.	Тур.	Max.	Unit
SCL clock frequency	f <sub>SCL</sub>	0	_	400	kHz
Hold time (Start Condition)	t <sub>HDSTA</sub>	0.6	1	_	μs
Low period of the SCL clock	t <sub>LOW</sub>	1.3		_	μs
High period of the SCL clock	t <sub>HIGH</sub>	0.6		_	μs
Set-up time (Repeated Start Condition)	t <sub>SUSTA</sub>	0.6	ı	_	μs
Data hold time	t <sub>HDDAT</sub>	0	_	0.9	μs
Data set-up time	t <sub>SUDAT</sub>	100	_	_	ns
Rise time of both SDA and SCL signals	t <sub>R</sub>	_	_	300	ns
Fall time of both SDA and SCL signals	t <sub>F</sub>	_	_	300	ns
Set-up time (Stop Condition)	t <sub>susto</sub>	0.6	_	_	μs
Bus free time between a Stop and Start Condition	t <sub>BUF</sub>	1.3		_	μs

# DLCKP1 / DLCKM1, DLOPx1 / DLOMx1



(Output load capacitance: 8 pF)

Item	Symbol	Min.	Тур.	Max.	Unit	Remarks
DLCK clock duty		40	50	60	%	DCK freq = 297 MHz (Max.)
DLO setup time	t <sub>SUDO</sub>	400	_	_	ps	Data Rate 297 MHz DDR
DLO hold time	t <sub>HDDO</sub>	400	_	_	ps	Data Rate 297 MHz DDR


# I/O Equivalent Circuit Diagram

### $\square$ : External pin

Symbol	Equivalent circuit	Symbol	Equivalent circuit
INCK	VDDMx VSSMx	XVS XHS	Digital VSSMx
XCLR XCE XMASTER XTRIG SLAMODE	Digital input VSSMx	SDI / SDA SCK / SCL	Digital I/O THE VSSMX
SDO	Digital output VSSMx		
VCP1 VCP2	Analog VSSHx	VRLOFG VRLTRX VRLSEL VRLTRG	Analog I/O VSSHx
VBGR	Analog VSSHx	DLOPx1 DLOMx1 DCKP1 DCKM1 x: C to F	Data output VSSMx

### **Spectral Sensitivity Characteristics**

(Excludes lens characteristics and light source characteristics.)




### **Image Sensor Characteristics**

 $(AV_{DD} = 3.3 \text{ V}, OV_{DD} = 1.8 \text{ V}, DV_{DD} = 1.2 \text{ V}, All-pixel scan mode, AD: 12 bit, Tj = 60 °C, Gain = 0 dB)$ 

Item		Symbol	Min.	Тур.	Max.	Unit	Measurement method	Remarks
Sensitivity	Sensitivity		3967 (970)	4687 (1146 )	_	Digit (mV)	1	1/30 s storage
Sensitivity	R/G	RG	0.47	I	0.62	_	2	
ratio	B/R	BG	0.29		0.44	_	2	
Saturation sig	Saturation signal		4094 (1001 *1)		_	Digit (mV)	3	Zone 0 to II'
Video eignel	SH01				20	%	4	Zone 0, I
Video signal s	snading	SH2D	1	_	25	%	4	Zone 0 to II'
Dark signal		Vdt			0.61 (0.15)	Digit (mV)	5	1/30 s storage
Dark signal shading		ΔVdt			1.02 (0.25)	Digit (mV)	6	1/30 s storage
PLS (Parasitic Lig	ht Sensitivity)	Sm	_	_	-93.9	dB	7	Zone II'

- Note) 1. Converted value into mV using 1Digit = 0.2445 mV for 12-bit output.
  - 2. The video signal shading is the measured value in the wafer status and does not include characteristics of the seal glass.

### **Zone Definition of Video Signal Shading**



### **Image Sensor Characteristics Measurement Method**

#### **Measurement Conditions**

In the following measurements, the device drive conditions are at the typical values of the bias conditions and clock voltage conditions.

In the following measurements, spot pixels are excluded and, unless otherwise specified, the optical black (OB) level is used as the reference for the signal output, which is taken as the value of the signal output of the measurement system.

### **Color Coding of Physical Pixel Array**

The primary color filters of this image sensor are arranged in the layout shown in the figure below. Gr and Gb represent the G signal on the same line as the R and B signals, respectively. The Gb signal and B signal lines and the R signal and Gr signal lines are output successively.

Gb	В	Gb	В
R	Gr	R	Gr
Gb	В	Gb	В
R	Gr	R	Gr

Color Coding Diagram

### **Definition of standard imaging conditions**

◆ Standard imaging condition I:

Use a pattern box (luminance:  $706 \text{ cd/m}^2$ , color temperature of 3200 K halogen source) as a subject. (Pattern for evaluation is not applicable.) Use a testing standard lens with CM500S (t = 1.0 mm) as an IR cut filter and image at F5.6. The luminous intensity to the sensor receiving surface at this point is defined as the standard sensitivity testing luminous intensity.

Standard image condition II:

Image a light source (color temperature of 3200 K) with a uniformity of brightness within 2 % at all angles. Use a testing standard lens with CM500S (t = 1.0 mm) as an IR cut filter. The luminous intensity is adjusted to the value indicated in each testing item by the lens diaphragm.

Standard image condition III:

Image a light source (color temperature of 3200 K) with a uniformity of brightness within 2 % at all angles. Use a testing standard lens (exit pupil distance -100 mm) with CM500S (t = 1.0 mm) as an IR cut filter. The luminous intensity is adjusted to the value indicated in each testing item by the lens diaphragm.

#### **Measurement Method**

#### 1. Sensitivity

Set the measurement condition to the standard imaging condition I. After setting the electronic shutter mode with a shutter speed of 1/100 s, measure the Gr and Gb signal outputs (VGr, VGb) at the center of the screen, and substitute the values into the following formula.

$$S = (VGr + VGb) / 2 \times 100 / 30 [mV]$$

#### 2. Sensitivity ratio

Set the measurement condition to the standard imaging condition II. After adjusting the average value of the Gr and Gb signal outputs to 573 mV, measure the R signal output (VR [mV]), the Gr and Gb signal outputs (VGr, VGb [mV]) and the B signal output (VB [mV]) at the center of the screen in frame readout mode, and substitute the values into the following formulas.

#### 3. Saturation signal

Set the measurement condition to the standard imaging condition II. After adjusting the luminous intensity to 10 times the intensity with the average value of the Gr and Gb signal outputs, 573 mV, measure the minimum values of the Gr, Gb, R and B signal outputs.

#### 4. Video signal shading

Set the measurement condition to the standard imaging condition III. With the lens diaphragm at F2.8, adjust the luminous intensity so that the average value of the Gr and Gb signal outputs are 573 mV. Then measure the maximum value (Gmax [mV]) and the minimum value (Gmin [mV]) of the Gr and Gb signal outputs, and substitute the values into the following formula.

$$SH = (Gmax - Gmin) / 573 \times 100 [\%]$$

#### 5. Dark signal

With the device junction temperature of 60  $^{\circ}$ C and the device in the light-obstructed state, divide the output difference between 1/3 s integration at 3 frame/s and 1/30 s integration at 30 frame/s by 9, and calculate the signal output converted to 1/30 s integration. Measure the average value of this output (Vdt [mV]).

#### 6. Dark signal shading

Measure the maximum value (Vdmax [mV]) and the minimum value (Vdmin [mV]) of the dark signal output with the device junction temperature of 60 °C and the device in the light-obstructed state and 1/30 s integration. The measuring values substitute into the following formula.

$$\Delta Vdt = Vdmax - Vdmin [mV]$$

#### 7. PLS

Set the measurement condition to the standard imaging condition II, the Gr and Gb output signal Vave measured by standard image condition. Then, adjust the luminous intensity to 500 times the intensity with average value of the Gr and Gb signal output, Vave. When the charge drain is executed be the electronic shutter and the condition that not be readout from photo diode to analog memory, readout by dropping to 1/113 frame rate.

$$Sm = 20 \times log ((Vsm / Vave) \times (1 / 500) \times (1 / 113)) [dB]$$

### **Setting Registers Using Serial Communication**

### **Description of Setting Registers (4-wire)**

The serial data input order is LSB-first transfer. The table below shows the various data types and descriptions.

### Serial Data Transfer Order


Chip ID	Start address	Data	Data	Data	
(8 bit)	(8 bit)	(8 bit)	(8 bit)	(8 bit)	(8 bit)

### Type and Description

Туре	Description
	Chip ID: 02 Write: 02h / Read: 82h
	Chip ID: 03 Write: 03h / Read: 83h
	Chip ID: 04 Write: 04h / Read: 84h
	Chip ID: 05 Write: 05h / Read: 85h
	Chip ID: 06 Write: 06h / Read: 86h
	Chip ID: 07 Write: 07h / Read: 87h
	Chip ID: 08 Write: 08h / Read: 88h
	Chip ID: 09 Write: 09h / Read: 89h
Chip ID	Chip ID: 0A Write: 0Ah / Read: 8Ah
	Chip ID: 0B Write: 0Bh / Read: 8Bh
	Chip ID: 0C Write: 0Ch / Read: 8Ch
	Chip ID: 0D Write: 0Dh / Read: 8Dh
	Chip ID: 0E Write: 0Eh / Read: 8Eh
	Chip ID: 0F Write: 0Fh / Read: 8Fh
	Chip ID: 10 Write: 10h / Read: 90h
	Chip ID: 11 Write: 11h / Read: 91h
	Chip ID: 12 Write: 12h / Read: 92h
	Designate the address according to the Register Map. When using a communication method
Address	that designates continuous addresses, the address is automatically incremented from the
	previously transmitted address.
Data	Input the setting values according to the Register Map.


### **Register Communication Timing (4-wire)**

Perform serial communication in sensor standby mode or within communication period. For the registers marked "V" in the item of Reflection timing, when the communication is performed in the communication period shown in the figure below they are reflected by frame reflection timing. For the registers noted "Immediately" in the item of Reflection timing, the settings are reflected when the communication is performed.




#### Register Write and Read (4-wire)

- ◆ Follow the communication procedure below when writing registers.
  - (1) Set XCE Low to enable the chip's communication function. Serial data input is executed using SCK and SDI.
  - (2) Transmit data in sync with SCK 1 bit at a time from the LSB using SDI. Transfer SDI in sync with the falling edge of SCK. (The data is loaded at the rising edge of SCK.)
  - (3) Input the Chip ID (CID = 02h to 12h) to the first byte. If the Chip ID differs, subsequent data is ignored.
  - (4) Input the start address to the second byte. The address is automatically incremented.
  - (5) Input the data to the third and subsequent bytes. The data in the third byte is written to the register address designated by the second byte, and the register address is automatically incremented thereafter when writing the data for the fourth and subsequent bytes. Normal register data is loaded to the inside of the sensor and established in 8-bit units.
  - (6) The register values starting from the register address designated by the second byte are output from the SDO pin. The register values before the write operation are output. The actual register values are the input data.
  - (7) Set XCE High to end communication.
- ◆ Follow the communication procedure below when reading registers.
  - Set XCE Low to enable the chip's communication function. Serial data input is executed using SCK and SDI.
  - (2) Transmit data in sync with SCK 1 bit at a time from the LSB using SDI. Transfer SDI in sync with the falling edge of SCK. (The data is loaded at the rising edge of SCK.)
  - (3) Input Chip ID (CID = 82h to 92h) to the first byte. If the Chip ID differs, subsequent data is ignored.
  - (4) Input the start address to the second byte. The address is automatically incremented.
  - (5) Input data to the third and subsequent bytes. Input dummy data in order to read the registers. The dummy data is not written to the registers. To read continuous data, input the necessary number of bytes of dummy data.
  - (6) The register values starting from the register address designated by the second byte are output from the SDO pin. The input data is not written, so the actual register values are output.
  - (7) Set XCE High to end communication.
- Note) When writing data to multiple registers with discontinuous addresses, access to undesired registers can be avoided by repeating the above procedure multiple times.



#### Serial Communication (Continuous Addresses)




Serial Communication (Discontinuous Addresses)

SONY

### Description of Setting Registers (I<sup>2</sup>C)

The serial data input order is MSB-first transfer. The table below shows the various data types and descriptions.



Pin connection of serial communication

This sensor can be set two slave addresses with the common I<sup>2</sup>C bus by switching the polarity of SLAMODE Pin.

### SLAVE Address (SLAMODE = 0)

MSB	,						LSB
0	0	1	0	0	0	0	R/W

### SLAVE Address (SLAMODE = 1)

MSB							LSB
0	0	1	1	0	1	0	R/W

<sup>\*</sup> R/W is data direction bit

### R/W

R/W bit	Data direction	
0	Write (Master → Sensor)	
1	Read (Sensor → Master)	


### I<sup>2</sup>C pin description

Symbol	Pin No.	Description	
SCL (common to SCK)	L3	Serial clock input	
SDA (common to SDI)	М3	Serial data communication	

### Register Communication Timing (I<sup>2</sup>C)

In I<sup>2</sup>C communication system, communication can be performed excluding during the period when communication is prohibited from the falling edge of XVS to 4H after.


For the registers marked "V" in the item of Reflection timing, when the communication is performed in the communication period shown in the figure below they are reflected by frame reflection timing. For the registers noted "Immediately" in the item of Reflection timing, the settings are reflected when the communication is performed. Using REG\_HOLD function is recommended for register setting using I<sup>2</sup>C communication. For REG\_HOLD function, see "Register Transmission Setting" in "Description of Functions".



SONY IMX264LQR-C


#### I<sup>2</sup>C Communication Protocol

I<sup>2</sup>C serial communication supports a 16-bit register address and 8-bit data message type.




#### Communication protocol


Data is transferred serially, MSB first in 8-bit units. After each data byte is transferred, A (Acknowledge) /  $\overline{A}$  (Negative Acknowledge) is transferred. Data (SDA) is transferred at the clock (SDL) cycle. SDA can change only while SCL is Low, so the SDA value must be held while SCL is High. The Start Condition is defined by SDA changing from High to Low while SCL is High. When the Stop Condition is not generated in the previous communication phase and Start Condition for the next communication is generated, that Start Condition is recognized as a Repeated Start Condition.



Start Condition




Stop Condition



Repeated Start Condition

After transfer of each data byte, the Master or the sensor transmits an Acknowledge / Negative Acknowledge and release (does not drive) SDA. When Negative Acknowledge is generated, the Master must immediately generate the Stop Condition and end the communication.




Acknowledge and Negative Acknowledge

### I<sup>2</sup>C Serial Communication Read/Write Operation

This sensor supports the following four read operations and two write operations.

#### **Single Read from Random Location**


The sensor has an index function that indicates which address it is focusing on. In reading the data at an optional single address, the Master must set the index value to the address to be read. For this purpose it performs dummy write operation up to the register address. The upper level of the figure below shows the sensor internal index value, and the lower level of the figure shows the SDA I/O data flow. The Master sets the sensor index value to M by designating the sensor slave address with a write request, then designating the address (M). Then, the Master generates the Start Condition. The Start Condition is generated without generating the Stop Condition, so it becomes the Repeated Start Condition. Next, when the Master sends the slave address with a read request, the sensor outputs an Acknowledge immediately followed by the index address data on SDA. After the Master receives the data, it generates a Negative Acknowledge and the Stop Condition to end the communication.



Single Read from Random Location

#### **Single Read from Current Location**

After the slave address is transmitted by a write request, that address is designated by the next communication and the index holds that value. In addition, when data read/write is performed, the index is incremented by the subsequent Acknowledge/Negative Acknowledge timing. When the index value is known to indicate the address to be read, sending the slave address with a read request allows the data to be read immediately after Acknowledge. After receiving the data, the Master generates a Negative Acknowledge and the Stop Condition to end the communication, but the index value is incremented, so the data at the next address can be read by sending the slave address with a read request.




Single Read from Current Location



#### **Sequential Read Starting from Random Location**


In reading data sequentially, which is starting from an optional address, the Master must set the index value to the start of the addresses to be read. For this purpose, dummy write operation includes the register address setting. The Master sets the sensor index value to M by designating the sensor slave address with a read request, then designating the address (M). Then, the Master generates the Repeated Start Condition. Next, when the Master sends the slave address with a read request, the sensor outputs an Acknowledge followed immediately by the index address data on SDA. When the Master outputs an Acknowledge after it receives the data, the index value inside the sensor is incremented and the data at the next address is output on SDA. This allows the Master to read data sequentially. After reading the necessary data, the Master generates a Negative Acknowledge and the Stop Condition to end the communication.



Sequential Read Starting from Random Location

#### **Sequential Read Starting from Current Location**

When the index value is known to indicate the address to be read, sending the slave address with a read request allows the data to be read immediately after the Acknowledge. When the Master outputs an Acknowledge after it receives the data, the index value inside the sensor is incremented and the data at the next address is output on SDA. This allows the Master to read data sequentially. After reading the necessary data, the Master generates a Negative Acknowledge and the Stop Condition to end the communication.



Sequential Read Starting from Current Location

### **Register Map**

This sensor has a total of 4352 bytes of registers, composed of registers with address 00h to FFh that correspond to Chip ID = 02h to 12h. Use the initial values for empty address. Some registers must be change from the initial values, so the sensor control side should be capable of setting 4352 bytes.

There are three different register reflection timings.

About the Reflection timing column of the Register Map, registers noted as "I" are reflected immediately after writing to register, registers noted as "S" are set during standby mode and reflected after standby canceled, registers noted as "V" are reflected at "Fame reflection register reflection timing" on the figure described in the section of "Setting Registers with Serial Communication".

Do not perform communication to addresses not listed in the Register Map. Doing so may result in operation errors.

# Chip ID = 02 (Write: Chip ID = 02h, Read: Chip ID = 82h, I<sup>2</sup>C: 30\*\*h)

Please refer to the other register map file of another file for the register that has not been described.

Address					Default value after reset		Reflection
4-wire	I <sup>2</sup> C	bit	Register Name Description	Description	By register	By address	timing
		0	STANDBY [0]	Standby mode 0: Normal operation 1: Standby	1		I
		1		Fixed to 0	0		_
00h		2		Fixed to 0	0		_
	3000h	3		Fixed to 0	0	01h	_
	ŀ	4		Fixed to 0	0		_
		5		Fixed to 0	0		_
		6		Fixed to 0	0		_
	•	7		Fixed to 0	0		_
		0	REGHOLD [0]	Register hold (Function not to update V reflection registers) 0: Invalid 1: Valid	0		I
		1		Fixed to 0	0		_
08h	3008h	2		Fixed to 0	0	00h	_
		3		Fixed to 0	0		_
		4		Fixed to 0	0		_
		5		Fixed to 0	0		_
		6		Fixed to 0	0		_
		7		Fixed to 0	0		_
	300Ah	0	XMSTA [0]	Setting of master mode operation 0: Master mode operation start 1: Master mode operation stop	1		ı
		1		Fixed to 0	0	1	_
0A		2		Fixed to 0	0	01h	_
		3		Fixed to 0	0		_
		4		Fixed to 0	0		_
		5		Fixed to 0	0		_
		6		Fixed to 0	0		_
		7		Fixed to 0	0		_
0Bh	-	0	TRIGEN [0]	Global shutter mode setting 0: Normal mode 1: Trigger mode	0		S
		1		Fixed to 0	0		
		2		Fixed to 0	0		_
	300Bh	3		Fixed to 0	0	00h	_
	Ī	4		Fixed to 0	0	]	_
		5		Fixed to 0	0	]	
	Ī	6		Fixed to 0	0		_
		7		Fixed to 0	0		_



Address					Default value after reset		Reflection
4-wire	I <sup>2</sup> C	bit	Register Name Description	By register	By address	timing	
0Dh	300Dh	0		Drive mode setting of V direction	0		S
		1	WINMODE [3:0]	0h: All-pixel 1h: 1/2 Subsampling mode Ch: Full-HD	0		
		2	WINNOBE [5.0]		0		
		3		Others: Setting prohibited	0		
				Drive mode setting of H direction			
		4	HMODE[0]	0: All-pixel 1: 1/2 Subsampling mode	0		S
		5		Fixed to 0	0		_
		6		Fixed to 0	0		_
		7		Fixed to 0	0		_
				Vertical (V) direction readout			
		0	VREVERSE [0]	inversion control	0		S
			== [2]	0: Normal 1: Inverted			
				Horizontal (H) direction readout			S
		1	HREVERSE [0]	inversion control	0		
OFF	2005			0: Normal 1: Inverted		001-	
0Eh	300Eh	2		Fixed to 0	0	00h	
		3		Fixed to 0	0		_
		4		Fixed to 0	0		
		5		Fixed to 0	0		_
		6		Fixed to 0	0		
		7		Fixed to 0	0		
		0		LSB	0082Eh	2Eh	V
		1		When sensor master mode vertical span setting. (Number of operation lines count from 1)			
		2					
10h	3010h	3					
1011	301011	4					
		5					
		6					
		7					
		0	VMAX [19:0]			08h	
11h	3011h	1					
		2					
		3					
		4					
		5					
		6					
		7					
12h	3012h	0					
		1					
		2					
		3		MSB		00h	
		4		Fixed to 0	0		
		5		Fixed to 0	0		
		6		Fixed to 0	0	1	
		7		Fixed to 0	0		



Add	Iress	1.7	D N	5	Default after		Reflection
4-wire	I <sup>2</sup> C	bit	Register Name	Description	By register	By address	timing
		0		LSB			
		1					
	14h 3014h	2					
14h		3				5Eh	
1411	301411	4				5En	
		5					
		6		When sensor master mode			
		7	HMAX [15:0]	horizontal span setting.	015Eh		S
		0	11 IIVI/AX [10.0]	(Number of operation clocks count from	OTSETT		3
		1		1)		01h	
		2					
15h	3015h	3					
1011	301311	4				0111	
		5					
		6					
		7		MSB			
		0		The value is set according to			
			CKSEL [0]	drive mode.	0		S
				0: All-pixel, ROI, 1/2 Subsampling			
				1: 1080p-Full HD			
		1		Fixed to 0	0		
19h	3019h	2		Fixed to 0	0	00h	<u> </u>
1		3		Fixed to 0	0		
		4		Fixed to 0	0		_
		5		Fixed to 0	0	-	
1		6 7		Fixed to 0 Fixed to 0	0	-	
					U		
		1	TOUT1SEL[1:0]	TOUT1 pin setting	0h		S
		2		Oh: Low fixed 3h: Pulse output		-	
26h	3026h	3	TOUT2SEL [1:0]	TOUT2 pin setting Oh: Low fixed 3h: Pulse output	0h		S
2011	3020N	4		Fixed to 0	0	00h	
		5		Fixed to 0	0		_
		6		Fixed to 0	0		
		7		Fixed to 0	0		_



Add	Iress				Defaul		D 6 .:
4-wire	I <sup>2</sup> C	bit	Register Name	Description	By register	By address	Reflection timing
		0 1 2	TRIG_TOUT1_SEL [2:0]	TOUT1 pin setting Oh: Low fixed 1h: Pulse1 output	0h		S
206	20206	3		Fixed to 0	0	006	
29h	3029h	4 5 6	TRIG_TOUT2_SEL [2:0]	TOUT2 pin setting Oh: Low fixed 2h: Pulse2 output	0h	00h	S
		7		Fixed to 0	0		
		0		Fixed to 0	0		_
	•	1		Fixed to 0	0		
		2		Fixed to 0	0		
		3		Fixed to 0	0		
36h	3036h	4 5	SYNCSEL	XHS, XVS pin setting 0h: Normal Output 3h: Hi-Z	0h	C0h	S
		6		Fixed to 1	1	1	_
		7		Fixed to 1	1	1	_
		0	PULSE1_EN_NOR [0]	Pulse1 output in normal mode 0: Disable 1: Enable	0		S
		1	PULSE1_EN_TRIG [0]	Pulse1 output in trigger mode 0: Disable 1: Enable	0		S
6Dh	306Dh	2	PULSE1_POL	Pulse1 polarity selection 0: High active 1: Low active	0	00h	S
		3		Fixed to 0	0	4	
		4		Fixed to 0	0		
		5		Fixed to 0	0		_
		6		Fixed to 0	0	-	
		7		Fixed to 0 LSB	0		
70h	3070h	1 2 3 4 5 6 7		Pulse1 active period start		00h	
71h 3071h	0 1 2 3 4 5 6 7	PULSE1_UP [19:0]	timing setting Designated in line units from reference point (For details, see the "Pulse Output Function")	00000h	00h	S	
72h 3072	3072h	0 1 2 3 4		MSB Fixed to 0	0	- 00h	
		5 6		Fixed to 0	0		_
				Fixed to 0	0		
		7		Fixed to 0	0		



Add	Iress				Default after		Reflection
4-wire	I <sup>2</sup> C	bit	Register Name	Description	By register	By address	timing
74h	3074h	0 1 2 3 4 5 6 7		LSB Pulse1 active period end		00h	
75h	75h 3075h -	0 1 2 3 4 5 6	PULSE1_DN [19:0]	timing setting Designated in line units from readout start (For details, see the "Pulse Output Function")	00000h	00h	S
76h		0 1 2 3 4		MSB Fixed to 0	0	00h	
		5 6 7		Fixed to 0 Fixed to 0 Fixed to 0	0 0 0		
		0	PULSE2_EN_NOR [0]	Pulse2 output in normal mode 0: Disable 1: Enable Pulse2 output in trigger mode	0		S
		2	PULSE2_EN_TRIG [0] PULSE2_POL [0]	0: Disable 1: Enable Pulse2 polarity selection	0		S
79h	3079h	3	FOLGEZ_FOL [0]	0: High active 1: Low active Fixed to 1	0	00h	S
		4 5 6		Fixed to 0 Fixed to 0 Fixed to 0	0 0		<u> </u>
		7		Fixed to 0	0		_
7Ch	307Ch	1 2 3 4 5 6		LSB Pulse2 active period start		00h	
7Dh	307Dh	0 1 2 3 4 5 6 7	PULSE2_UP [19:0]	timing setting Designated in line units from reference point (For details, see the "Pulse Output Function")	00000h	00h	S
7Eh	307Eh	0 1 2 3 4 5		MSB Fixed to 0 Fixed to 0	0	00h	<del>-</del>
				Fixed to 0 Fixed to 0	0		<u> </u>



Add	Iress				Default after i		Reflection	
4-wire	I <sup>2</sup> C	bit	Register Name	Description	By register	By address	timing	
80h	3080h	0 1 2 3 4 5 6 7		LSB Pulse2 active period end		00h		
81h	3081h	0 1 2 3 4 5 6 7	PULSE2_DN [19:0]	timing setting Designated in line units from reference point (For details, see the "Pulse Output Function")	00000h	00h	S	
82h	3082h	0 1 2 3 4 5		MSB Fixed to 0 Fixed to 0	0	00h		
		6		Fixed to 0	0		_	
		7		Fixed to 0	0		_	
89h	3089h	[7:0]	INCKSEL0 [7:0]	Set according to INCK frequency and drive mode.	20h	20h	S	
8Ah	308Ah	[7:0]	INCKSEL1 [7:0]	Set according to INCK frequency and drive mode.	00h	00h	S	
8Bh	308Bh	[7:0]	INCKSEL2 [7:0]	Set according to INCK frequency and drive mode.	20h	20h	S	
8Ch	308Ch	[7:0]	INCKSEL3 [7:0]	Set according to INCK frequency and drive mode.	00h	00h	S	
8Dh	308Dh	0 1 2 3 4 5 6 7		LSB		0Ah		
8Eh	308Eh	0 1 2 3 4 5 6 7	SHS [19:0]	Storage time adjustment Designated in line unit	0000Ah	00h	V	
8Fh	308Fh	0 1 2 3 4 5 6 7		MSB Fixed to 0	0 0 0	00h		
9Eh	309Eh	[7:0]	GTWAIT [7:0]	The value is set according to drive mode.  08h: All-pixel, ROI, 1/2 Subsampling 06h: 1080p-Full HD	0Ah	0Ah	S	

Ado	Iress	la ia	Desistes News	Description	Defaul after	t value reset	Reflection
4-wire	I <sup>2</sup> C	bit	Register Name	Description	By register	By address	timing
A0h	30A0h	[7:0]	GSDLY [7:0]	The value is set according to drive mode.  04h: All-pixel, ROI, 1/2 Subsampling  02h: 1080p-Full HD	08h	08h	S
		0	VINT_EN	Setting of Interrupt mode in Trigger Mode 0: V interrupt is disable 1: V interrupt is enable	1		S
		1		Fixed to 0	0		_
AAh	30AAh	2		Fixed to 0	0	01h	
		3		Fixed to 0	0		
		4		Fixed to 0	0		
		5		Fixed to 0	0		
		6		Fixed to 0	0		
		7		Fixed to 0	0		
		0	LOWLAGTRG	Selection of trigger mode 0: Except for Fast trigger mode 1: Fast trigger mode	0		S
		1		Fixed to 0	0		_
		2		Fixed to 0	0		_
AEh	30AEh	3		Fixed to 0	0	00h	_
		4		Fixed to 0	0		_
		5		Fixed to 0	0		
		6		Fixed to 0	0		
		7		Fixed to 0	0		_
AFh	30AFh	[7:0]		The value is set according to drive mode.  0Eh: All-pixel, ROI, 1/2 Subsampling 0Ah: 1080p-Full HD	06h	06h	S

# Chip ID = 03 (Write: Chip ID = 03h, Read: Chip ID = 83h, $I^2$ C: 31\*\*h)

# Chip ID = 04 (Write: Chip ID = 04h, Read: Chip ID = 84h, I<sup>2</sup>C: 32\*\*h)

Add	Iress	bit	Degister Neme	Description	Default after i		Reflection
4-wire	I <sup>2</sup> C	DIL	Register Name	Description	Ву	Ву	timing
- ******					register	address	
		0		LSB			
		1					
	04h 3204h	2		Gain setting			
04h		3		0 dB (000d) to 48 dB (480d)		00h	
0	020	4	GAIN [8:0]	0.1 dB Step	000h	00	V
		5		(Refer to Address 12h about detail of			
		6	-	Reflection Timing.)			
		7					
		0		MSB			
		1		Fixed to 0	0		_
		2		Fixed to 0	0		
05h	3205h	3		Fixed to 0	0	00h	_
0311	320311	4		Fixed to 0	0	0011	_
		5		Fixed to 0	0		_
		6		Fixed to 0	0		_
		7		Fixed to 0	0		_
12h	3212h	[7:0]	GAINDLY	Setting of Gain Reflection Timing at Normal mode.  08h: Gain reflect at the frame  09h: Gain reflect at the next frame  (Same timing as SHS reflecting output.)  Others: Setting prohibited	00h	00h	S
		0		LSB			
		1	1				
		2	1				
		3					
54h	3254h	4				3Ch	
		5		Black level offset value setting			_
		6	BLKLEVEL [11:0]	Recommended value:	03Ch		S
		7		0F0h: 12 bit:			
		0					
		1					
		2	1				
	0055	3	1	MSB		001	
55h	3255h	4		Fixed to 0	0	00h	_
		5		Fixed to 0	0	1	_
		6		Fixed to 0	0	1	_
		7		Fixed to 0	0	1	_

# Chip ID = 05 (Write: Chip ID = 05h, Read: Chip ID = 85h, I2C: 33\*\*h)

Please refer to the other register map file for the register that has not been described.

Ado	dress					t value reset	Reflection	
4-wire	I <sup>2</sup> C	bit	Register Name	Description	By register	By address	timing	
		0	FID0_ROIH1ON [0]	The horizontal setting of FID0 ROI area (1, 1) 0: Disable 1: Enable	0	V	V	
00h	3300h	1	FID0_ROIV1ON [0]	The vertical setting of FID0 ROI area (1, 1) 0: Disable 1: Enable	0	00h	I	
		[7:2]		Fixed to 0	00h		_	
10h	3310h	[7:0]		Designation of horizontal cropping position		00h		
		[4:0]	FID0_ROIPH1 [12:0]	for FID0 on area (1, 1)	0000h		V	
11h	3311h	[4.0]		*Set the value of multiple of 4		00h		
		[7:5]		Fixed to 0h	0h		_	
12h	3312h	[7:0]		Designation of vertical cropping position		00h		
13h	3313h	[3:0]	FID0_ROIPV1 [11:0]	for FID0 on area (1, 1)  *Set the value of multiple of 4	000h	00h	I	
		[7:4]		Fixed to 0h	0h		_	
14h	3314h	[7:0]		Designation of horizontal cropping size		00h		
15h	3315h	[4:0]	FID0_ROIWH1 [12:0]	for FID0 on area (1, 1)  *Set the value of multiple of 4	0000h	00h	V	
		[7:5]		Fixed to 0h	0h		_	
16h	3316h	[7:0]		Designation of vertical cropping size		00h		
17h	17h 3317h		FID0_ROIWV1 [11:0]	for FID0 on area (1, 1) *Set the value of multiple of 4	000h	00h	1	
		[7:4]		Fixed to 0h	0h		_	

# Chip ID = 06 (Write: Chip ID = 06h, Read: Chip ID = 86h, I<sup>2</sup>C: 34\*\*h)

Please refer to the other register map file for the register that has not been described.

# Chip ID = 07 (Write: Chip ID = 07h, Read: Chip ID = 87h, $I^2$ C: 35\*\*h)

Please refer to the other register map file for the register that has not been described.

Chip ID = 08 (Write: Chip ID = 08h, Read: Chip ID = 88h, 
$$I^2$$
C: 36\*\*h)

Please refer to the other register map file for the register that has not been described.

### Chip ID = 09 (Write: Chip ID = 09h, Read: Chip ID = 89h, $1^2$ C: 37\*\*h)

Please refer to the other register map file for the register that has not been described.

### Chip ID = 0A (Write: Chip ID = 0Ah, Read: Chip ID = 8Ah, $I^2$ C: 38\*\*h)

Please refer to the other register map file for the register that has not been described.

#### Chip ID = 0B (Write: Chip ID = 0Bh, Read: Chip ID = 8Bh, $I^2$ C: 39\*\*h)

SONY

IMX264LQR-C

Chip ID = 0C (Write: Chip ID = 0Ch, Read: Chip ID = 8Ch, I<sup>2</sup>C: 3A\*\*h)

Please refer to the other register map file for the register that has not been described.

Chip ID = 0D (Write: Chip ID = 0Dh, Read: Chip ID = 8Dh, I<sup>2</sup>C: 3B\*\*h)

Please refer to the other register map file for the register that has not been described.

Chip ID = 0E (Write: Chip ID = 0Eh, Read: Chip ID = 8Eh, I<sup>2</sup>C: 3C\*\*h)

Please refer to the other register map file for the register that has not been described.

Chip ID = 0F (Write: Chip ID = 0Fh, Read: Chip ID = 8Fh, 1<sup>2</sup>C: 3D\*\*h)

Please refer to the other register map file for the register that has not been described.

Chip ID = 10 (Write: Chip ID = 10h, Read: Chip ID = 90h,  $I^2$ C:  $3E^{**}h$ )

Please refer to the other register map file for the register that has not been described.

Chip ID = 11 (Write: Chip ID = 11h, Read: Chip ID = 91h,  $I^2$ C:  $3F^{**}h$ )

Please refer to the other register map file for the register that has not been described.

Chip ID = 12 (Write: Chip ID = 12h, Read: Chip ID = 92h,  $I^2$ C:  $40^{**}h$ )

## **Readout Drive Modes**

The table below lists the operating modes available with this sensor. (Each value is the Max. frame rate of the each number of ch.)

Drive	Frame	Data rate [Gbps]	Serial LVDS ch <sup>*1</sup>	A /D		Number of recording pixels		Total number of pixels <sup>2</sup>		Number of INCK in 1H		
mode	rate [frame/s]			A/D conversion	н	V	н	V	INCK: 37.125 MHz	INCK: 74.25 MHz	INCK: 54 MHz	
All pixel	35.7	2.376	4	12	2448	2048	2656	2088	498.0	996.0	724.4	
All pixel (Vertical / Horizontal 1/2 subsampling)	88.4	2.376	4	12	1224	1024	2112	1060	396.0	792.0	576.0	
LID4000-	60	4.700	,	40	1000	4000	2200	4405	550.0	1100.0	_	
HD1080p	30	1.782	4	12	1920	1080	4400	1125	1100.0	2200.0	_	
ROI	*4	2.376	4	12	*3	*3	2656	*4	498.0	996.0	724.4	

<sup>\*1</sup> The data rate of each output channel is value that is obtained by total data rate divided by the number of channels.

Example) In All-pixel 35.7 [frame/s] mode: 2.376 [Gbps] / 4 = 594 [Mbps]

For the setting value to register HMAX / VMAX, see the section of each drive mode settings


<sup>\*3</sup> Designated cropping area (ROI)

<sup>\*4</sup> See the section of "ROI mode"

SONY

#### Sync code

The sync code is added immediately before and after "dummy signal + OB signal + effective pixel data" and then output. The sync code is output in order of 1st, 2nd, 3rd and 4th. The fixed value is output for 1st to 3rd. (BLK: Blanking period)




Sync Code Output Timing

### **List of Sync Code**

Sync code	1st code	2nd code	3rd code	4th code
Syric code	12 bit	12 bit	12 bit	12 bit
SAV (Valid line)	FFFh	000h	000h	800h
EAV (Valid line)	FFFh	000h	000h	9D0h
SAV (Invalid line)	FFFh	000h	000h	AB0h
EAV (Invalid line)	FFFh	000h	000h	B60h

#### **Sync Code Output Timing**

The sensor output signal passes through the internal circuits and is output with a latency time (system delay) relative to the horizontal sync signal. This system delay value is undefined for each line, so refer to the sync codes output from the sensor and perform synchronization.




# **Image Data Output Format**


## All-pixel scan

Register List of All-pixel scan mode

			Initial	Setting value	=		
Address	bit	Register name	Value	AD = 12 bit	Remarks		
			raido	35.7 [frame/s]			
Chip ID =	02h						
0Dh	[3:0]	WINMODE	0h	0h	All-pixel mode		
0Dh	[4]	HMODE	0	0	All-pixel		
10h	[7:0]						
11h	[7:0]	VMAX	82Eh	828h	2088 line		
12h	[3:0]						
14h	[7:0]	HMAX	15Eh	3E4h			
15h	[7:0]	HIVIAX	15En	3E4N			
19h	[0]	CKSEL	0	0			
				INCK = 37.125 MHz: 10h			
89h	[7:0]	INCKSEL0	20h	INCK = 54 MHz: 16h			
				INCK = 74.25 MHz: 10h			
				INCK = 37.125 MHz: 02h			
8Ah	[7:0]	INCKSEL1 00h		INCKSEL1	00h	INCK = 54 MHz: 00h	
				INCK = 74.25 MHz: 00h			
				INCK = 37.125 MHz: 10h			
8Bh	[7:0]	INCKSEL2	20h	INCK = 54 MHz: 16h			
				INCK = 74.25 MHz: 10h			
				INCK = 37.125 MHz: 02h			
8Ch	[7:0]	INCKSEL3	00h	INCK = 54 MHz: 00h			
				INCK = 74.25 MHz: 00h			
9Eh	[7:0]	GTWAIT	0Ah	08h			
A0h	[7:0]	GSDLY	08h	04h			
Chip ID =	04h						
54h	[7:0]	BLKLEVEL	03Ch	0F0h	Recommended		
55h	[3:0]	DLNLEVEL	บงษา	UFUII	value		



Pixel Array Image Drawing in All-pixel scan Mode




Drive Timing Chart for Serial Output in All-pixel Scan Mode




### 1080p-Full HD mode

Register List of 1080p-Full HD mode

		Register	Initial	Setting	y value			
Address	bit	name	Value	AD =	12 bit	Remarks		
		Hame	value	60 [frame/s]	30 [frame/s]			
Chip ID =	02h							
0Dh	[3:0]	WINMODE	0h	C	Ch .	1080p- FULL HD mode		
0Dh	[4]	HMODE	0		0			
10h	[7:0]							
11h	[7:0]	VMAX	82Eh	46	5h	1125 line		
12h	[3:0]							
14h	[7:0]	HMAX	1556	44Ch	9096			
15h	[7:0]	HIVIAX	15Eh	44Cn	898h			
19h	[0]	CKSEL	0	•	1			
89h	[7:0]	INCKSEL0	20h	INCK = 37.1 INCK = 74.2	25 MHz: 18h 25 MHz: 0Ch			
8Ah	[7:0]	INCKSEL1	00h	INCK = 37.1. INCK = 74.2	25 MHz: 00h 25 MHz: 00h			
8Bh	[7:0]	INCKSEL2	20h	INCK = 37.1. INCK = 74.2	25 MHz: 10h 25 MHz: 10h			
8Ch	[7:0]	INCKSEL3	00h	INCK = 37.1. INCK = 74.2	25 MHz: 02h 25 MHz: 00h			
9Eh	[7:0]	GTWAIT	0Ah	06	6h			
A0h	[7:0]	GSDLY	08h	02	2h			
Chip ID =	04h							
54h 55h	[7:0] [3:0]	BLKLEVEL	03Ch	OF	-Oh	Recommended value		



Pixel Array Image Drawing in 1080p-Full HD Mode



Drive Timing Chart for Serial Output in 1080p-Full HD Mode



#### **ROI** mode

This Sensor has ROI function that signals are cut out and read out in multi arbitrary position.

Cropping position can set maximum 1 area that specified by horizontal 1 point and vertical 1 point, regarding effective pixel start position as origin (0, 0) in all pixel scan mode. Cropping is available from All-pixel scan mode and horizontal period are fixed to the value for this mode.

This cropped area by horizontal cropping setting (ROI (1, 1)) is output with left justified and that extends the horizontal blanking period. In vertical cropping area (ROI (1, 1)), the number of image data is also output from cropping start line and the frame rate can be adjusted by changing the number of input XVS lines in slave mode or changing register VMAX in master mode.

One invalid frame is generated when the ROI area changing size or cropping address.

ROI image is shown in the figure below.

In case of Vertical / Horizontal 1/2 subsampling mode, this sensor doesn't support ROI mode.





Image Drawing of Designated Areas in ROI Mode



**Details of Image Drawing** 



# Register List of ROI mode

Please set All-pixel scan mode to the settings other than the following.

				Setting value					
Address	bit	Register name	Initial	AD = 12 bit	Remarks				
Address	DIL	Register flame	Value	*1 [frame/s]	Remarks				
Chip ID =	Ոշի			i [ilane/s]	1				
0Dh	[3:0]	WINMODE	0h	0h	All-pixel mode				
0Dh	[4]	HMODE	0	0	All-pixel				
10h	[7:0]		Ť	, and the second	7				
11h	[7:0]	VMAX	82Eh	*1					
12h	[3:0]	-							
14h	[7:0]								
15h	[7:0]	HMAX	15Eh	3E4h					
19h	[0]	CKSEL	0	0					
				INCK = 37.125 MHz: 10h					
89h	[7:0]	INCKSEL0	20h	INCK = 54 MHz: 16h					
	,			INCK = 74.25 MHz: 10h					
				INCK = 37.125 MHz: 02h					
8Ah	[7:0]	INCKSEL1	00h	INCK = 54 MHz: 00h					
				INCK = 74.25 MHz: 00h					
				INCK = 37.125 MHz: 10h					
8Bh	[7:0]	INCKSEL2	20h	INCK = 54 MHz: 16h					
				INCK = 74.25 MHz: 10h					
				INCK = 37.125 MHz: 02h					
8Ch	[7:0]	INCKSEL3							
			INCK = 74.25 MHz: 00h						
9Eh	[7:0]	GTWAIT	0Ah	08h					
A0h	[7:0]	GSDLY	08h	04h					
Chip ID =	04h								
54h	[7:0]	BLKLEVEL	03Ch	0F0h	Recommended				
55h	[3:0]	DEIXELVEE	00011	01 011	value				
Chip ID =	05h	1	ı						
	[0]	FID0_ROIH1ON	0	The horizontal setting of FID0 ROI area (1, 1)					
00h	[0]	20	Ŭ	0: Disable 1: Enable					
	[1]	FID0_ROIV1ON	0	The vertical setting of FID0 ROI area (1, 1)					
			_	0: Disable 1: Enable					
10h	[7:0]	FID0_ROIPH1	0000h	Designation of horizontal cropping position for FID0 on area (1, 1)					
11h	[4:0]	_		*Set the value of multiple of 4					
12h	[7:0]	FID0_ROIPV1 000h		Designation of vertical cropping position for FID0 on area (1, 1)					
13h	[3:0]			*Set the value of multiple of 4					
14h	[7:0]	FID0_ROIWH1	0000h	Designation of horizontal cropping size for FID0 on area (1, 1)					
15h	[4:0]		*Set the value of multiple of 4						
16h	[7:0]	FID0_ROIWV1	000h	Designation of vertical cropping size for FID0 on area (1, 1)					
17h	[3:0]			*Set the value of multiple of 4					



#### **Restrictions on ROI mode**

The register settings should satisfy following conditions:

\* Do not designate area like be overlap.

ROIPH1 + ROIWH1 ≤ 2464d

ROIPV1 + ROIWV1 ≤ 2056d

- \* Set the horizontal and vertical setting in multiple of 4.
- \* Minimum width of the window is as below.

ROIWH1 ≥ 260d

ROIWV1 ≥ 4d

#### Frame rate on ROI mode

Frame rate [ frame/s ] =  $1 / (("Number of lines per frame" or VMAX) \times (1 H period))$ 

- \* Number of lines per frame or VMAX = ROIWV1 + 32
- \* 1 H period:

Calculate by number of INCK in 1 H and the period of INCK.


The example of ROI setting is shown below.

ROIWV1 = 600

ROIWV1 = 4 (minimum value)

### Frame rate List of each setting

Register settings No. in register list		Frame rate [frame/s]				
	1 H period [µs]	Total number of ROI: 600 [line]	Total number of ROI: 4 [line]			
*1	13.414	117.9	2070.7			



Drive Timing Chart for Serial Output in ROI Mode


### Vertical / Horizontal 1/2 Subsampling mode

V direction and H direction must be set in this mode.

# Register List of Vertical / Horizontal 1/2 subsampling mode

Please set All-pixel scan mode to the settings other than the following.

	Pagistar		1-24-1	Setting value					
Address	bit	Register name	Initial Value	AD = 12 bit	Remarks				
		name	value	88.4 [frame/s]					
Chip ID =	= 02h								
0Dh	[3:0]	WINMODE	0h	1h	Subsampling				
UDII	[3.0]	WINWODE	UII	111	mode				
0Dh	[4]	HMODE	0	1	Subsampling				
UDII	[4]	TIMODL	U	-	mode				
10h	[7:0]								
11h	[7:0]	VMAX	82Eh	424h	1060 line				
12h	[3:0]								
14h	[7:0]	HMAX	15Eh	318h					
15h	[7:0]	ПІЛАЛ	ISEN	31011					



Pixel Array Image Drawing in Vertical / Horizontal 1/2 subsampling mode

# **Description of Various Function**

#### Standby mode


This sensor stops its operation and goes into standby mode which reduces the power consumption by writing "1" to the standby control register STANDBY. Standby mode is also established after power-on or other system reset operation.

### Register List of Standby setting

Register	Register details			Initial			
	Chip ID	Address (): I <sup>2</sup> C	bit	value	Setting value	Remarks	
STANDBY	02h	00h (3000h)	[0]	1h	1h: Standby 0h: Operating	Register communication is executed even in standby mode.	

The serial communication registers hold the previous values. However, the address registers transmitted in standby mode are overwritten. The serial communication block operates even in standby mode, so standby mode can be canceled by setting the STANDBY register to "0". Some time is required for sensor internal circuit stabilization after standby mode is canceled. For details on the sequence of setting and cancel of standby mode, see the sensor setting flow after power on.

After standby mode is canceled, a normal image is output from the 9 frames after internal regulator stabilization (1 ms or more).



Sequence from Standby Cancel to Stable Image Output



#### **Slave Mode and Master Mode**

The sensor can be switched between slave mode and master mode.

The switching is made by the XMASTER pin. Establish the XMASTER pin status before canceling the system reset. (Do not switch this pin status during operation.)

Input a vertical sync signal to XVS and input a horizontal sync signal to XHS when a sensor is in slave mode.

For sync signal interval, input data lines to output for vertical sync signal and 1H period designated in each operating mode for horizontal sync signal. See the section of "Readout Drive mode" for the number of output data line and 1H period.

Set the XMSTA register to "0" in order to start the operation after setting to master mode. In addition, set the count number of sync signal in vertical direction by the VMAX [19:0] register and the clock number in horizontal direction by the HMAX [15:0] register. See the description of operation mode for details of the section of "Readout Drive Modes".


#### Pin Processing

Pin name	Pin processing	Operation mode	Remarks	
XMASTER pin	Low fixed	Master mode	High: OV <sub>DD</sub>	
	High fixed	Slave mode	Low: GND	

#### Register List of Slave Mode and Master Mode

	Reg	ister details		Initial			
Register	Chip ID	Address (): I <sup>2</sup> C	Bit	value	Setting value	Remarks	
XMSTA		0Ah (300Ah)	[0]	1h	1h: Master operation ready (Initial value) 0h: Master operation start	The master operation starts by setting 0.	
		10h (3010h)	[7:0]			Line number per frame	
VMAX [19:0]	02h	11h (3011h)	[7:0]	0082Eh	See the item of each drive mode	designated (Master mode and Slave	
		12h (3012h)	[3:0]			mode common setting.)	
HMAX [15:0]		14h (3014h)	[7:0]	015Eh	See the item of	Clock number per line designated	
		15h (3015h)	[7:0]	UISEN	each drive mode	(Master mode and Slave mode common setting.)	

#### XVS / XHS Output Waveform in Master Mode



SONY IMX264LQR-C

# **Gain Adjustment Function**


### PGC

The Programmable Gain Control (PGC) of this device consists of the analog block and digital block. The total of analog gain and digital gain can be set up to 48 dB by the GAIN [8:0] register setting. The value which is ten times the gain is set to register.

#### Example)

When set to 6 dB:


 $6 \times 10 = 60d$ , GAIN = 03Ch



### Register List of Gain setting

Register	Register details			Initial	Setting value	Remarks
	Chip ID	Address (): I <sup>2</sup> C	bit	value	Setting range	Remarks
GAIN [8:0]	04h	04h (3204h)	[7:0]	000h	000h to 1E0h	Setting value:
	0411	05h (3205h)	[0]	00011	(0d to 480d)	Gain [dB] × 10

Gain Reflection Timing is changed by the set value of GAINDLY as shown below.



Gain Reflection Timing

# **Black Level Adjustment Function**

The black level offset (offset variable range: 000h to 1FFh) can be added relative to the data in which the digital gain modulation was performed by the BLKLEVEL [11:0] register. When the BLKLEVEL [11:0] setting is increased by 1 LSB, the black level is increased by 1 LSB.

\* Use with values shown below is recommended.12 bit output: 0F0h (240 d)

# Register List of Black level adjustment

Register	Register details			1 (4) - 1		
	Chip ID	Address (): I <sup>2</sup> C	bit	Initial value	Setting value	
BLKLEVEL [11:0]	1 045	54h (3254h)	[7:0]	02 <b>C</b> b	000h to EEEh	
	04h	55h (3255h)	[3:0]	03Ch	000h to FFFh	


**SONY** IMX264LQR-C


# **Horizontal / Vertical Normal Operation and Inverted Operation**

The sensor readout direction (normal / inverted) in vertical direction can be switched by the VREVERSE register setting and sensor readout direction (normal / inverted) in horizontal direction can be switched by the HREVERSE register setting. See the section of "Readout Drive Modes" for the order of readout lines in normal and inverted modes.


## Register List of Readout Drive Direction setting


Register	Register details			1 :4: 1		
	Chip ID	Address (): I <sup>2</sup> C	bit	Initial value	Setting value	
VREVERSE	026	0Eh	[0]	0h	0h: Normal (Initial value) 1h: Inverted	
HREVERSE	02h	(300Eh)	[1]	0h	0h: Normal (Initial value) 1h: Inverted	





Normal and Inverted Drive Outline in Vertical Direction (TOP VIEW)





Normal and Inverted Drive Outline in Horizontal Direction (TOP VIEW)

#### **Shutter and Integration Time Settings**

This sensor has a global shutter function that integrates to all line collectively by using memory in each pixel. This sensor has a variable electronic shutter function that can control the integration time in line units for adjust the exposure time. This sensor transferred signal to memory in pixel after the exposure (memory transfer), then this sensor performs output in which readout operation is performed sequentially for each line in sync with the XHS signal. This sensor has trigger mode that can be controlled exposure start timing and memory transfer timing by trigger.

Note) For integration time control, an image which reflects the setting is output from the frame after the setting changes.

In this item, the shutter operation and storage time are shown as in the figure below with the time sequence on the horizontal axis and the vertical address on the vertical axis. For simplification, shutter and readout operation are noted in line units.




Image Drawing of Global Shutter (Normal mode) Operation




Image Drawing of Global Shutter (Sequential Trigger mode) Operation

### **Global Shutter (Normal Mode) Operation**

The integration time can be controlled by varying the electronic shutter timing. In the electronic shutter settings, the integration time is controlled by the SHS [19:0] register. For setting value of SHS [19:0], see the table "List of Exposure Setting". When the sensor is operating in slave mode, the number of lines per frame is determined by the XVS interval (number of lines), using the input XHS interval as the line unit. When the sensor is operating in master mode, the number of lines per frame is determined by the VMAX [19:0] register. The number of lines per frame differs according to the operating mode.

## **Calculation Formula of Exposure Time**

Exposure time [s] = (1 H period) × (Number of lines per frame - SHS) + 13.73 [ $\mu$ s]<sup>\*1</sup>: Exposure time error (t<sub>OFFSET</sub>)

### Register List of Shutter setting

	Reg	ister details	S	Initial		
Register	Chip ID	Address (): I <sup>2</sup> C	bit	value	Setting value	
		10h (3010h)	[7:0]			
VMAX [19:0]		11h (3011h)	[7:0]	0082Eh	Set the number of lines per frame (only in master mode)	
	02h	12h (3012h)	[3:0]			
	0211	8Dh (308Dh)	[7:0]	0000Ah	Sets the shutter sweep time.	
SHS [19:0]		8Eh (308Eh)	[7:0]		memory wait time to (Number of lines per frame - 1)	
		8Fh (308Fh)	[3:0]		- 1)	

IMX264LQR-C



# List of Exposure Setting

	memory	Number of	SHS	Exposure	4 ch LVDS / Max	ximum frame rate
Drive mode	wait time	lines per frame	Setting value	Setting value	Frame rate [frame/s]	Actually exposure [ms]*4
	[H]	[DEC]	[DEC]	[H]	12 bit	12 bit
			2087	1		0.027
			2086	2		0.041
All-pixel	10	2088		•••	35.7	
			11	2077		27.866
			10	2078		27.879
		1125	1124	1		0.029
			1123	2	60	0.043
1080p-Full HD	6		•••			•••
			7	1118		16.577
			6	1119		16.592
			V <sub>TR</sub> -1	1		0.027
			V <sub>TR</sub> -2	2		0.041
ROI	10	V <sub>TR</sub> *1	•••		*2	
			11	V <sub>TR</sub> -11		*3
			10	V <sub>TR</sub> -10		

 $<sup>^{*1}</sup>$  V<sub>TR</sub> = ROIWV1 + 32

<sup>&</sup>lt;sup>14</sup> INCK frequency is input by typical value, and t<sub>OFFSET</sub> (13.73 [µs]) is included.




Image Drawing of Global Shutter (Normal Mode)

<sup>&</sup>lt;sup>\*2</sup> For the frame rate, see the section "ROI mode" in "Readout Drive Mode".

Conform to the calculation formula of exposure time. (Number of lines per frame =  $V_{TR}$ )



### **Global Shutter (Sequential Trigger Mode) Operation**

The integration time can be controlled by varying the pulse width that is input to XTRIG pin. The pulse width designated in XHS unit [H]. For the transition from normal mode to trigger mode, set 1 to the register TRIGEN. The XVS input signal is ignored during trigger mode operating. In case of inputting trigger continuously, there are period which prohibit the trigger rise input ( $t_{TGPD}$ ) and fall input ( $t_{GES}$ ) based on the previous trigger rise. When the trigger rise is input before the rise input prohibited period ( $t_{TGPD}$ ), interrupt operation starts. This function is slave mode only. The number of lines per frame differs according to the operating mode.

# **Calculation Formula of Exposure Time**

Exposure time [s] =  $(XTRIG low level pulse width [H]^{*2}) + 13.73 [\mu s]^{*1}$ 

\*1: Exposure time error (t<sub>OFFSET</sub>)

### Register List of shutter setting

	Reg	ister details	3			
Register	Chip ID	Address (): l <sup>2</sup> C bit Address		Initial value	Setting value	
XMSTA	02h	0Ah (300Ah)	[0]	1h	Setting of master mode operation  0: Master mode operation start  1: Master mode operation stop	
TRIGEN	02h	0Bh (300Bh)	[0]	0h	0h: Global shutter (normal mode) 1h: Global shutter (trigger mode)	
VINT_EN	02h	AAh (30AAh)	[0]	1h	Setting of Interrupt mode in Trigger Mode 0: V interrupt is disable 1: V interrupt is enable	

#### Parameter List of Global Shutter (Sequential Trigger Mode)

Item	Symbol	Min.	Тур.	Max.	Unit
Integration start delay	t <sub>TGST</sub>	2	_	3	Н
Integration end delay	t <sub>TGED</sub>	2 + t <sub>OFFSET</sub>	_	3 + t <sub>OFFSET</sub>	Н
Pulse width	t <sub>TGSE</sub>	1	_	_	Н
Next trigger fall prohibited period (All-pixel, ROI, 1/2 Subsampling)	<b>.</b>	11	_	_	Н
Next trigger fall prohibited period (1080p Full-HD)	- t <sub>TGES</sub>	9	_	_	Н
Next trigger rise prohibited period (All-pixel)		2092	_	_	
Next trigger rise prohibited period (1/2 Subsampling)		1064	_	_	. н
Next trigger rise prohibited period (1080p Full-HD)	- t <sub>TGPD</sub>	1125	_	_	
Next trigger rise prohibited period (ROI)		$V_{TR}^{*1}$	_	_	
Data output delay (All-pixel / ROI)	<b>+</b>	_	19	_	Н
Data output delay (1080p-Full HD)	t <sub>TGDLY</sub>	_	15	_	''

 $<sup>^{*1}</sup>$  V<sub>TR</sub> = ROIWV1 + 32

<sup>&</sup>lt;sup>\*2</sup>: Low level pulse width is counted by XHS pulse.




Image Drawing of Global Shutter (Sequential Trigger Mode)

#### **Interrupt Operation**

In case of VINT\_EN = 1h, the image drawing when the interrupt operation is generated is shown below. When the trigger is raised again and the next frame is output during read of the frame for which read was started by a trigger rise (Frame 1 in the figure below), Frame 1 becomes an invalid frame. Trigger timing of interrupt generating corresponds to  $t_{TGPD}$  in Parameter List of Global Shutter (Trigger Mode)

In case of VINT\_EN = 0h, both of the rising edge and the falling edge of the trigger signal are ignored in  $t_{TGPD}$  (Prohibit period).

But in case of VINT\_EN = 0h, both of the rising edge and the falling edge of the trigger signal which are input during GSDLY (CID = 02h, Address = A0h) + 5H before the end of read out aren't ignored.




Image Drawing of Interrupt Operation in Global Shutter (Sequential Trigger Mode)

# **Global Shutter (Fast Trigger Mode) Operation**

Fast trigger mode is the trigger mode that starts exposure at fall of XTRIG immediately. This mode supports Master mode only.

### **Calculation Formula of Exposure Time**

Exposure time [s] = (XTRIG low level pulse width [ $\mu$ s]) + 13.73 [ $\mu$ s]<sup>\*1</sup>: Exposure time error ( $t_{OFFSET}$ )

# Register List of shutter setting

	Reg	ister details	3			
Register	Chip ID	Address (): I <sup>2</sup> C Address	bit	Initial value	Setting value	
XMSTA		0Ah (300Ah)	[0]	1h	Setting of master mode operation  0: Master mode operation start  1: Master mode operation stop	
TRIGEN		0Bh (300Bh)	[0]	0h	0h: Global shutter (normal mode) 1h: Global shutter (trigger mode)	
SYNCSEL	02h 36h (3036h)		[5:4]	0h	XHS, XVS pin setting 0h: Normal Output 3h: Hi-Z	
LOWLAGTRG		AEh (30AEh)	[0]	0h	Selection of trigger mode  0: Except for Fast trigger mode  1: Fast trigger mode	

# Parameter List of Global Shutter (Fast Trigger Mode)

Item		Min.	Тур.	Max.	Unit	
Integration start delay	t <sub>TGST</sub>	_	_	0.05	μs	
Integration end delay	t <sub>TGED</sub>	_	_	0.05 + t <sub>OFFSET</sub>	μs	
Pulse width	t <sub>TGSE</sub>	0.05	_	_	μs	
Next trigger rise / fall prohibited period (All-pixel)		2108	_	_		
Next trigger rise / fall prohibited period (1/2 Subsampling)	t <sub>TGPD</sub>	1080	_	_	Н	
Next trigger rise / fall prohibited period (1080p Full-HD)		1141	_	_		
Next trigger rise / fall prohibited period (ROI)		V <sub>TR</sub> <sup>*1</sup>	_	_		
Data output delay (All-pixel / ROI)		_	19	_	Н	
Data output delay (1080p-Full HD)	t <sub>TGDLY</sub>	_	15	_	''	

 $<sup>^{*1}</sup>$  V<sub>TR</sub> = ROIWV1 + 32




Image Drawing of Global Shutter (Fast Trigger Mode) (4-wire)



#### **Mode Transitions of Global Shutter Operation**

The sensor can be switched between normal mode and trigger mode in global shutter operation by setting the register TRIGEN. The sensor will transition to normal mode or trigger mode 20H after the register TRIGEN is set. (The XVS and XTRIG input during transition are prohibited.)

In case of Fast Trigger mode, the mode transition must be done via sensor standby.

#### **Transition from Normal Mode to Sequential Trigger Mode**

The sensor will transition from normal mode to trigger mode after setting 1d to register TRIGEN. The XVS input is ignored after transition to trigger mode. Trigger input is prohibited for a 20H period after the register TRIGEN is set. When TRIGEN is set during data read, read operation is stopped and that frame becomes an invalid frame.

\* The communication is available till 9 H period only when sensor transition to the Trigger mode.




Image Drawing of Transition from Normal Mode to Sequential Trigger Mode

#### **Transition from Sequential Trigger Mode to Normal Mode**

The sensor will transition from trigger mode to normal mode after setting 0d to register TRIGEN. Start XVS input after transition to normal mode. Set TRIGEN after Next trigger rise prohibited period ( $t_{TGPD}$ ) has passed. When TRIGEN is set before  $t_{TGPD}$ , read operation is stopped and that frame becomes an invalid frame.




Image Drawing of Transition from Sequential Trigger Mode to Normal Mode



### **Pulse Output Function**

This sensor has a pulse output function that indicates each state of shutter operation. The pulse output from TOUT1 pin and TOUT2 pin. The rise timing and fall timing of pulse are set by Register. For the reference point (The timing when register value set to 0) to be set, see the table "List of Reference point". The pulse is output asynchronously with other signals on the basis of the sensor internal timing shown in the "List of Reference point". This function doesn't support Fast Trigger mode.

# Register List of Pulse Output Function

	Register details		Initial					
Register	Chip ID	Address (): I <sup>2</sup> C	bit	value	Setting value			
TOUT1SEL [1:0]		26h	[1:0]	0h	TOUT1 pin setting Oh: Low fixed 3h: Pulse output			
TOUT2SEL [1:0]		(3026h)	[3:2]	0h	TOUT2 pin setting Oh: Low fixed 3h: Pulse output			
TRIG_TOUT1_SEL [2:0]		29h	[2:0]	0h	TOUT1 pin output selection Oh: Low fixed 1h: Pulse1 output			
TRIG_TOUT2_SEL [2:0]		(3029h)	[6:4]	0h	TOUT2 pin output selection Oh: Low fixed 2h: Pulse2 output			
PULSE1_EN_NOR			[0]	0	Pulse1 enable in normal mode 0: disable 1: enable			
PULSE1_EN_TRIG		6Dh (306Dh)	[1]	0	Pulse1 enable in trigger mode 0: disable 1: enable			
PULSE1_POL	02h		[2]	0	Pulse1 polarity selection 0: High active 1: Low active			
		70h (3070h)	[7:0]					
PULSE1_UP [19:0]		71h (3071h)	[7:0]	00000h	Pulse1 active period start timing setting Designated in line units from reference point			
		72h (3072h)	[3:0]					
		74h (3074h)	[7:0]					
PULSE1_DN [19:0]		75h (3075h)	[7:0]	00000h	Pulse1 active period end timing setting Designated in line units from reference point			
		76h (3076h)	[3:0]					
PULSE2_EN_NOR			[0]	0	Pulse2 enable in normal mode 0: disable 1: enable			
PULSE2_EN_TRIG		79h	[1]	0	Pulse2 enable in trigger mode 0: disable 1: enable			
PULSE2_POL		(3079h)	[2]	0	Pulse2 polarity selection 0: High active 1: Low active			
			[3]	0	Fixed to 1			
		7Ch (307Ch)	[7:0]	00000h				
PULSE2_UP [19:0]		7Dh (307Dh)	[7:0]		Pulse2 active period start timing setting Designated in line units from reference point			
		7Eh (307Eh)	[3:0]					
		80h (3080h)	[7:0]	00000h				
PULSE2_DN [19:0]		81h (3081h)	[7:0]		Pulse2 active period end timing setting Designated in line units from reference point			
		82h (3082h)	[3:0]					



#### List of Reference Point

	Normal mode	Trigger mode
Reference point of Pulse1	XVS fall edge in N frame	Fall edge of input trigger
Reference point of Pulse2	XVS fall edge in N +1 frame	Rise edge of input trigger




Image Drawing of Pulse Output Function in Global Shutter (Normal Mode)

In normal mode, TOUT1 and TOUT2 are output alternately each time inputting XVS.




Image Drawing of Pulse Output Function in Global Shutter (Sequential Trigger Mode)

# **Signal Output**

### **Output Pins**

This sensor supports Low voltage LVDS serial (4 ch) DDR output.

Output Pins for Low Voltage LVDS Serial

	Low voltage LVDS serial DDR output				
Output pins	4 ch				
DLOPC1 / DLOMC1	Ch 3				
DLOPD1 / DLOMD1	Ch 1				
DLOPE1 / DLOME1	Ch 2				
DLOPF1 / DLOMF1	Ch 4				
DLCKP1 / DLCKM1	DCK1				

Low-voltage LVDS serial 4 ch output format is shown in the figure below.

When setting 4 ch, after four data of SAV is output in the order of CH1 to CH4 pixel data is repeatedly output in the same order and then four data of EAV is output in the same order to CH1 to CH4 respectively.


Data is sent MSB first. For details, see drive timing in each mode in the section of "Readout Drive Mode".

	4 ch										
DCK1											
CH1	SAV 1st	SAV 2nd	SAV 3rd	SAV 4th	Ро		P 4n	EAV 1st	EAV 2nd	EAV 3rd	EAV 4th
CH2	SAV 1st	SAV 2nd	SAV 3rd	SAV 4th	P 1		P 4n+1	EAV 1st	EAV 2nd	EAV 3rd	EAV 4th
CH3	SAV 1st	SAV 2nd	SAV 3rd	SAV 4th	P <sub>2</sub>	• • •	P 4n+2	EAV 1st	EAV 2nd	EAV 3rd	EAV 4th
CH4	SAV 1st	SAV 2nd	SAV 3rd	SAV 4th	P <sub>3</sub>	• • •	P 4n+3	EAV 1st	EAV 2nd	EAV 3rd	EAV 4th

Output Format of Low voltage LVDS Serial 4 ch

### **Output Pin Bit Width**

Sync code is output according to bit width.



Example of Data format in low-voltage LVDS serial 12-bit output

# **Output Signal Range**

The sensor output has either 12-bit gradation, but output is not performed over the full range, and the maximum output value is the "FFFh - 1" (12-bit output). The minimum value is 001h. The output range for each output gradation is shown in the table below. The maximum level and the minimum level are output only in the sync code. See the item of "Sync Codes" in the section of "Operating Modes" for the sync codes.

# Output Gradation and Output Range


Output gradation	Output value				
Output gradation	Min.	Max.			
12 bit	001h	FFEh			

## **Register Hold Setting**

Register setting can be transmitted with divided to several frames and it can be reflected globally at a certain frame by the register REGHOLD. Setting REGHOLD = 1 at the start of register communication period prevents the registers that are set thereafter from reflecting at the frame reflection timing. The registers that are set when setting REGHOLD = 1 are reflected globally by setting REGHOLD = 0 at the end of communication period of the desired frame to reflect the register.

## Register List of Register Hold

	Register details			Initial	
Register	Chip ID	Address (): I <sup>2</sup> C	bit	value	Setting value
REGHOLD	02h	08h (3008h)	[0]	0h	0h: Invalid 1h: Valid (Register hold)



Register Hold Setting

SONY

IMX264LQR-C

#### **Mode Transition**

The Mode transition between operations is shown below. These examples shown in case that setting is completed within one communication timing.

#### List of Mode Transition

Т	State	
ROI	Via the Standby state	
All-pixel	ROI	is unnecessary
<ul> <li>Transition between modes other than th</li> <li>Change the input frequency of INCK *1</li> <li>Change the register setting noted "S" in</li> </ul>	Via the standby state is necessary	

When changing input INCK frequency, care should be taken not to be input pulses whose width are shorter than the High / Low level width in front and behind of the INCK pulse at the frequency change. If the pulses above generate at the frequency change, change INCK frequency during system reset in the state of XCLR = Low, and then perform system clear in the state of XCLR = High following the item of "Power on sequence" in the section of "Power on / off sequence". Execute initial setting again because the register settings become default state after system clear.

SONY IMX264LQR-C

## **Other Function**

This sensor has the function as below. About detail, refer to each application note.

- Multi Frame Set Output mode (2 / 4 frame)
- Multi Exposure Trigger mode
- Driving Low Power Consumption at longtime exposure
- Simple Thermometer
- Gradation Compression
- Pattern Generator

## **Extension Function**

Use these function after enough checks and evaluation.


- Black Level Auto Adjuster Off
- Short Exposure Mode

## **Power-on and Power-off Sequence**

#### Power-on sequence

Follow the sequence below to turn On the power supplies.


- 1. Turn On the power supplies so that the power supplies rise in order of 1.2 V power supply (DVDD)  $\rightarrow$  1.8 V power supply (OVDD)  $\rightarrow$  3.3 V power supply (AVDD). In addition, all power supplies should finish rising within 200 ms.
- 2. The register values are undefined immediately after power-on, so the system must be cleared. Hold XCLR at Low level for 500 ns or more after all the power supplies have finished rising. (The register values after a system clear are the default values.)
  In addition, hold XCE to High level during this period. Rise XCE after 1.8 V power supply (OVDD), so hold XCE at High level until INCK is input.
- 3. Start the input of INCK after turning the level of XCLR into the high.
- 4. Make the sensor setting by register communication after the system clear. A period of 0 μs or more should be provided after setting XCLR High before inputting the communication enable signal XCE.



Power-on Sequence

## **Power-off Sequence**

Turn Off the power supplies so that the power supplies fall in order of 3.3 V power supply (AVDD)  $\rightarrow$  1.8 V power supply (OVDD)  $\rightarrow$  1.2 V power supply (DVDD). In addition, all power supplies should finish falling within 200 ms. Set each digital input pin (INCK, XCE, SCK, SDI, XCLR, XMASTER, XTRIG, SLAMODE, XVS, XHS) to 0 V or high impedance before the 1.8 V power supply (OVDD) falls.




Power-off Sequence

## **Sensor Setting Flow**

## **Setting Flow in Sensor Slave Mode**

The figure below shows operating flow in sensor slave mode.

For details of "Power on" to "System clear", see the item of "Power on sequence" in this section. For details of "Standby cancel" to "Wait for image stabilization", see the item of "Standby mode". "Standby setting (power save mode) can be made by setting the STANDBY register to "1" during "Operation".




Sensor Setting Flow (Sensor Slave Mode)

## **Setting Flow in Sensor Master Mode**

The figure below shows operating flow in sensor master mode.

For details of "Power on" to "System clear", see the item of "Power on sequence" in this section. For details of "Standby cancel" to "Wait for image stabilization", see the item of "Standby mode". In master mode, "Master mode start" by setting the master mode start register XMSTA to "0" after "Wait for internal regulator stabilization". "Standby setting (power save mode) can be made by setting the STANDBY register to "1" during "Operation". This time, set "master mode stop" by setting XMSTA to "1".




Sensor Setting Flow (Sensor Master Mode)

SONY

IMX264LQR-C


# **Peripheral Circuit**

## **Analog Power Pins**



**SONY** IMX264LQR-C


## **Digital Power Pins**



Pin D2, D15, H12, and K5 are analog power pins. But these pins can be connected to the digital power pins. So, it describe on this page. These pins can be separated from the digital power pins.

SONY IMX264LQR-C

# **Analog Other Pins**



SONY


IMX264LQR-C

## Digital I/O Pins

Pin H1, H2 are 3.3V GND. But, these pins are I/O terminal GND. So, these pins describe on this page.

SONY IMX264LQR-C

# **Output pins**



# **Spot Pixel Specifications**


(Tj = 60 °C)

		Maximum	distorted pixels in	Measurement			
Type of distortion	Level		0 to II'	Effective OB	Ineffective OB	method	Remarks
Black and white pixels at high light	30 % ≤	D	37	No evaluation	criteria applied	1	
White pixels in the dark	5.6 mV ≤	D	4:	35	No evaluation criteria applied	2	1/30 s storage
Black pixels at signal saturated		D ≤ 700 mV	0	No evaluation	criteria applied	3	

Note) 1. Zone is specified based on all-pixel drive mode

- 2. D...Spot pixel level
- 3. See the Spot Pixel Pattern Specifications for the specifications in which pixel and black pixel are close.

# **Sport Pixel Zone Definition**



## **Notice on White Pixels Specifications**

After delivery inspection of CMOS image sensors, cosmic radiation may distort pixels of CMOS image sensors, and then distorted pixels may cause white point effects in dark signals in picture images. (Such white point effects shall be hereinafter referred to as "White Pixels".) Unfortunately, it is not possible with current scientific technology for CMOS image sensors to prevent such White Pixels. It is recommended that when you use CMOS image sensors, you should consider taking measures against such White Pixels, such as adoption of automatic compensation systems for White Pixels in dark signals and establishment of quality assurance standards. Unless the Seller's liability for White Pixels is otherwise set forth in an agreement between you and the Seller, Sony Corporation or its distributors (hereinafter collectively referred to as the "Seller") will, at the Seller's expense, replace such CMOS image sensors, in the event the CMOS image sensors delivered by the Seller are found to be to the Seller's satisfaction, to have over the allowable range of White Pixels as set forth above under the heading "Spot Pixels Specifications", within the period of three months after the delivery date of such CMOS image sensors from the Seller to you; provided that the Seller disclaims and will not assume any liability after you have incorporated such CMOS image sensors into other products. Please be aware that Seller disclaims and will not assume any liability for (1) CMOS image sensors fabricated, altered or modified after delivery to you, (2) CMOS image sensors incorporated into other products, (3) CMOS image sensors shipped to a third party in any form whatsoever, or (4) CMOS image sensors delivered to you over three months ago. Except the above mentioned replacement by Seller, neither Sony Corporation nor its distributors will assume any liability for White Pixels. Please resolve any problem or trouble arising from or in connection with White Pixels at your costs and expenses.

#### [For Your Reference] The Annual Number of White Pixels Occurrence

The chart below shows the predictable data on the annual number of White Pixels occurrence in a single-story building in Tokyo at an altitude of 0 meters. It is recommended that you should consider taking measures against the annual White Pixels, such as adoption of automatic compensation systems appropriate for each annual number of White Pixels occurrence.

The data in the chart is based on records of past field tests, and signifies estimated number of White Pixels calculated according to structures and electrical properties of each device. Moreover, the data in the chart is for your reference purpose only, and is not to be used as part of any CMOS image sensor specifications.

#### **Example of Annual Number of Occurrence**

White Pixel Level (in case of integration time = 1/30 s) $(T_{j} = 60  ^{\circ}\text{C})$	Annual number of occurrence
5.6 mV or higher	11 pcs
10.0 mV or higher	7 pcs
24.0 mV or higher	4 pcs
50.0 mV or higher	2 pcs
72.0 mV or higher	2 pcs

- Note 1) The above data indicates the number of White Pixels occurrence when a CMOS image sensor is left for a year.
- Note 2) The annual number of White Pixels occurrence fluctuates depending on the CMOS image sensor storage environment (such as altitude, geomagnetic latitude and building structure), time (solar activity effects) and so on. Moreover, there may be statistic errors. Please take notice and understand that this is an example of test data with experiments that have being conducted over a specific time period and in a specific environment.
- Note 3) This data does not guarantee the upper limits of the number of White Pixels occurrence.

#### For Your Reference:

The annual number of White Pixels occurrence at an altitude of 3,000 meters is from 5 to 10 times more than that at an altitude of 0 meters because of the density of the cosmic rays. In addition, in high latitude geographical areas such as London and New York, the density of cosmic rays increases due to a difference in the geomagnetic density, so the annual number of White Pixels occurrence in such areas approximately doubles when compared with that in Tokyo.

Material No.03-0.0.8


#### **Measurement Method for Spot Pixels**

After setting to standard imaging condition II, and the device driver should be set to meet bias and clock voltage conditions. Configure the drive circuit according to the example and measure.

## 1. Black or white pixels at high light

After adjusting the luminous intensity so that the average value VG of the Gb / Gr signal outputs is 573 mV, measure the local dip point (black pixel at high light,  $V_{IB}$ ) and peak point (white pixel at high light,  $V_{IK}$ ) in the Gr / Gb / R / B signal output Vi (i = Gr / Gb / R / B), and substitute the value into the following formula.

Spot pixel level D = ((ViB or Vik) / Average value of Vi) x 100 [%]



Signal output waveform of R / G / B channel

#### 2. White pixels in the dark

Set the device to a dark setting and measure the local peak point of the signal output waveform, using the average value of the dark signal output as a reference.

#### 3. Black pixels at signal saturated

Set the device to operate in saturation and measure the local dip point, using the OB output as a reference.



Signal output waveform of R / G / B channel

## **Spot Pixel Pattern Specification**

White Pixel, Black Pixel and Bright Pixel are judged from the pattern whether they are allowed or rejected, and counted.

List of White Pixel, Black Pixel and Bright Pixel Pattern

No.	Pattern	White pixel Black pixel Bright pixel
1		Rejected
2		Rejected

Note) 1. "


" shows the position of white pixel, black pixel and bright pixel.

White pixel, black pixel and bright pixel are specified separately according the pattern.

(Example: If a black pixel and a white pixel is in the pattern No.1 respectively, they are not judged to be rejected.)

- 2. When one or more spot pixels indicated "Rejected" is selected and removed.
- 3. Spot pixels other than described in the table above are all counted including the number of allowable spot pixels by zone.

## Marking



Note: Following characters enter into "Y", and "Z". (No Au coat) Y: In English upper case character, One character Z: Number, single number

DRAWING No. AM-A264LQR (2D)

## **Notes On Handling**

#### 1. Static charge prevention

Image sensors are easily damaged by static discharge. Before handling be sure to take the following protective measures.

- (1) Either handle bare handed or use non-chargeable gloves, clothes or material. Also use conductive shoes.
- (2) Use a wrist strap when handling directly.
- (3) Install grounded conductive mats on the floor and working table to prevent the generation of static electricity.
- (4) Ionized air is recommended for discharge when handling image sensors.
- (5) For the shipment of mounted boards, use boxes treated for the prevention of static charges.

#### 2. Protection from dust and dirt

Image sensors are packed and delivered with care taken to protect the element glass surfaces from harmful dust and dirt. Clean glass surfaces with the following operations as required before use.

- (1) Perform all lens assembly and other work in a clean environment (class 1000 or less).
- (2) Do not touch the glass surface with hand and make any object contact with it. If dust or other is stuck to a glass surface, blow it off with an air blower. (For dust stuck through static electricity, ionized air is recommended.)
- (3) Clean with a cotton swab with ethyl alcohol if grease stained. Be careful not to scratch the glass.
- (4) Keep in a dedicated case to protect from dust and dirt. To prevent dew condensation, preheat or precool when moving to a room with great temperature differences.
- (5) When a protective tape is applied before shipping, remove the tape applied for electrostatic protection just before use. Do not reuse the tape.

#### 3. Installing (attaching)


- (1) If a load is applied to the entire surface by a hard component, bending stress may be generated and the package may fracture, etc., depending on the flatness of the bottom of the package. Therefore, for installation, use either an elastic load, such as a spring plate, or an adhesive.
- (2) The adhesive may cause the marking on the rear surface to disappear.
- (3) If metal, etc., clash or rub against the package surface, the package may chip or fragment and generate dust.
- (4) Acrylate anaerobic adhesives are generally used to attach this product. In addition, cyanoacrylate instantaneous adhesives are sometimes used jointly with acrylate anaerobic adhesives to hold the product in place until the adhesive completely hardens. (Reference)
- (5) Note that the sensor may be damaged when using ultraviolet ray and infrared laser for mounting it.

#### 4. Recommended reflow soldering conditions

The following items should be observed for reflow soldering.

(1) Temperature profile for reflow soldering

Control item	Profile (at part side surface)
1. Preheating	150 to 180 °C 60 to 120 s
2. Temperature up (down)	+4 °C/s or less (- 6 °C/s or less)
3. Reflow temperature	Over 230 °C 10 to 30 s Max. 5 °C/s
4. Peak temperature	Max. 240 ± 5 °C



#### (2) Reflow conditions

- (a) Make sure the temperature of the upper surface of the seal glass resin adhesive portion of the package does not exceed 245 °C.
- (b) Perform the reflow soldering only one time.
- (c) Finish reflow soldering within 72 h after unsealing the degassed packing. Store the products under the condition of temperature of 30 °C or less and humidity of 70 % RH or less after unsealing the package.
- (d) Perform re-baking only one time under the condition at 125 °C for 24 h.

#### (3) Others

- (a) Carry out evaluation for the solder joint reliability in your company.
- (b) After the reflow, the paste residue of protective tape may remain around the seal glass. (The paste residue of protective tape should be ignored except remarkable one.)
- (c) Note that X-ray inspection may damage characteristics of the sensor.

#### 5. Others

- (1) Do not expose to strong light (sun rays) for long periods, as the color filters of color devices will be discolored.
- (2) Exposure to high temperature or humidity will affect the characteristics. Accordingly avoid storage or use in such conditions.
- (3) This product is precision optical parts, so care should be taken not to apply excessive mechanical shocks or force.
- (4) Note that imaging characteristics of the sensor may be affected when approaching strong electromagnetic wave or magnetic field during operation.
- (5) Note that image may be affected by the light leaked to optical black when using an infrared cut filter that has transparency in near infrared ray area during shooting subjects with high luminance.


Material\_No.14-0.0.6

## **Package Outline**

L G A

226Pin

(Unit: mm)



# List of Trademark Logos and Definition Statements

# Exmor

\* Exmor is a trademark of Sony Corporation. The Exmor is a version of Sony's high performance CMOS image sensor with high-speed processing, low noise and low power dissipation by using column-parallel A/D conversion.

# **Pregius**

\* Pregius is a trademark of Sony Corporation. The Pregius is global shutter pixel technology for active pixel-type CMOS image sensors that use Sony's low-noise CCD structure, and realizes high picture quality.



# **Revision History**

Date of change	Revision	Page	Contain of Change
18-Sept-15	0.1.0	. ~9~	First edition (Preliminary version)
. с сорт то	01110	P1	Delete: "Preliminary"
		P7	Update:
			Optical Center figure.
		P15	Correction: TBD in the chart. (Power Consumption)
		P23	Correction: TBD in the chart. (Image Sensor Characteristics)
		P25	Correction: Number 2 - 5 item in "Measurement Method".
16-Oct-15	E15X05	P66	Correction: TBD in the chart. (Parameter List of Global Shutter)
		P86	Correction:
		P87	TBD in the chart. (Annual number of occurrence)  Correction:
		_	TBD in the chart. (Measurement Method for Spot Pixels) Update:
		P89	Marking. Update:
		P87	Package Outline
			First edition (Official version)  Correction:
29-Oct-15	E15X05A5X	P45	HD1080p deletes "INCK: 54MHz" values in the chart. (HD1080p is outside the support.)
		P23	Correction:
		1 25	Item of Sensitivity ratio.
		P25	Correction: Calculating formula of Sensitivity.
		P27, P30	Delete: The explanation about the register shich the reflection timing is "immediately"
		P34	Correction:
			Supplementary explanation of Register Map  Correction:
		P35 to P43	Reflection timing of Register Map
		P41, P66	Correction: Description of "LOWLAGTRG"
		P47	Correction: Pixel Array Image Drawing in All-pixel scan Mode
		P48	Correction:
		_	Drive Timing Chart in All-pixel scan Mode  Correction:
		P49	Pixel Array Image Drawing in 1080p-Full HD Mode
27-May-16	E15X05B65	P50	Correction: Drive Timing Chart in 1080p-Full HD Mode
		P53	Correction: Restriction on ROI mode
		P54	Correction: Drive Timing Chart in ROI Mode
		P55	Correction: Pixel Array Image Drawing in Vertical / Horizontal 1/2 Subsampling Mode
		P63	Correction: Contents in "List of Exposure Setting" table
		P64	Correction:
		P65	Item of "t <sub>TGSE</sub> " in Parameter List  Correction:
		P66	Sequential Trigger Mode Image Drawing  Correction:
			Item of "t <sub>TGSE</sub> " and "t <sub>TGED</sub> " in Parameter List  Correction:
		P67	Fast Trigger Mode Image Drawing
		P74	Correction: Contents in "List of Mode Transition" table
<u> </u>	ı		<u> </u>

# SONY

Date of change	Revision	Page	Contain of Change
		P75	Added:
		F/3	Description of Extension Function
		P81	Added:
		POI	Epexegesis of Pin D2, D15, H12 and K5
		P83	Added:
		P63	Epexegesis of Pin H1, H2
		P92	Update:
		F92	Package Out line figure
08-Jun-16	E15X05C66	P65	Correction:
00-34H-10	L 13/03000	- 00	Note of VINT_EN = 0h in Interrupt Operation

Sales: Shenzhen Sunnywale Inc, www.sunnywale.com, awin@sunnywale.com, Wechat: 9308762